

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT ~~C200967~~ **C201507**

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000100000-E	200	Lump Sum		CLEARING & GRUBBING .. ACRE(S)
000800000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
002200000-E	225	110	CY	UNCLASSIFIED EXCAVATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (11+27.00)
003600000-E	225	200	CY	UNDERCUT EXCAVATION
010600000-E	230	160	CY	BORROW EXCAVATION
013400000-E	240	3	CY	DRAINAGE DITCH EXCAVATION
015600000-E	250	1,050	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT
019600000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	6	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
034300000-E	310	56	LF	15" SIDE DRAIN PIPE
101100000-N	500	Lump Sum		FINE GRADING
122000000-E	545	10	TON	INCIDENTAL STONE BASE
148900000-E	610	85	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	200	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	17	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
255600000-E	846	75	LF	SHOULDER BERM GUTTER
257000000-N	SP	1	EA	MODIFIED CONCRETE FLUME
303000000-E	862	137.5	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
362800000-E	876	2	TON	PLAIN RIP RAP, CLASS I
364900000-E	876	1	TON	PLAIN RIP RAP, CLASS B

ItemNumber	Sec #	Quantity	Unit	Description
365600000-E	876	161	SY	FILTER FABRIC FOR DRAINAGE
402500000-E	901	8	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (D)
402500000-E	901	30.25	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
408200000-E	903	103	LF	SUPPORTS, WOOD
409600000-N	904	2	EA	SIGN ERECTION, TYPE D
410200000-N	904	5	EA	SIGN ERECTION, TYPE E
415800000-N	907	4	EA	DISPOSAL OF SIGN SYSTEM, WOOD
441200000-E	SP	256	SF	WORK ZONE SIGNS (STATIONARY)
441200000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	4	EA	WARNING FLAG SETS
444610000-E	SP	96	LF	BARRICADES (TYPE III)
600000000-E	1605	485	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	80	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	30	TON	SEDIMENT CONTROL STONE
601500000-E	1615	0.5	ACR	TEMPORARY MULCHING
601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
602900000-E	SP	300	LF	SAFETY FENCE
603000000-E	1630	105	CY	SILT EXCAVATION
603600000-E	1631	215	SY	MATTING FOR EROSION CONTROL
603800000-E	SP	600	SY	PERMANENT SOIL REINFORCEMENT MAT
604800000-E	SP	100	SY	FLOATING TURBIDITY CURTAIN
608400000-E	1660	0.5	ACR	SEEDING & MULCHING
608700000-E	1660	0.5	ACR	MOWING

ItemNumber	Sec #	Quantity	Unit	Description
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	0.25	TON	FERTILIZER TOPDRESSING
611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL