

**STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS**

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
-L-		
8+50.00	0	0
9+00.00	2	6
9+50.00	6	13
10+00.00	18	11
10+50.00	18	8
10+75.00 (BEG. BRIDGE)	0	2
11+79.00 (END BRIDGE)	0	15
12+00.00	6	15
12+50.00	30	72
13+00.00	18	43
13+50.00	5	9
14+00.00	2	2
14+10.71	0	0
TOTAL	105	196

Note: "Quantities are approximate only. The Resident Engineer will re-cross section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid."

