

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201364

ItemNumber	Sec #	Quantity	Unit	Description
000010000-N	800	Lump Sum		MOBILIZATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (25+80.65)
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
005700000-E	226	400	CY	UNDERCUT EXCAVATION
006300000-N	SP	Lump Sum		GRADING
008000000-E	SP	100	TON	CLASS IV SUBGRADE STABILIZA- TION
010600000-E	230	8,850	CY	BORROW EXCAVATION
013400000-E	240	350	CY	DRAINAGE DITCH EXCAVATION
019500000-E	265	400	CY	SELECT GRANULAR MATERIAL
019600000-E	270	200	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	10	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
070800000-E	310	88	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
080600000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
122000000-E	545	100	TON	INCIDENTAL STONE BASE
148900000-E	610	440	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	350	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	42	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
200000000-N	806	4	EA	RIGHT OF WAY MARKERS
202200000-E	815	112	CY	SUBDRAIN EXCAVATION
203300000-E	815	84	CY	SUBDRAIN FINE AGGREGATE
204400000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE
205500000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)

ItemNumber	Sec #	Quantity	Unit	Description
228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES
236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
255600000-E	846	265	LF	SHOULDER BERM GUTTER
303000000-E	862	625	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
364900000-E	876	15	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	715	SY	FILTER FABRIC FOR DRAINAGE
365900000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
441200000-E	SP	349	SF	WORK ZONE SIGNS (STATIONARY)
441220000-E	SP	69	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	2	EA	WARNING FLAG SETS
444610000-E	SP	96	LF	BARRICADES (TYPE III)
481000000-E	1205	8,800	LF	PAINT PAVEMENT MARKING LINES (4")
490000000-N	1252	30	EA	PERMANENT RAISED PAVEMENT MARKERS
600000000-E	1605	1,500	LF	TEMPORARY SILT FENCE
600600000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	180	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	240	TON	SEDIMENT CONTROL STONE
601500000-E	1615	3	ACR	TEMPORARY MULCHING
601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
602400000-E	1622	70	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS

ItemNumber	Sec #	Quantity	Unit	Description
602900000-E	SP	200	LF	SAFETY FENCE
603000000-E	1630	760	CY	SILT EXCAVATION
603600000-E	1631	210	SY	MATTING FOR EROSION CONTROL
603800000-E	SP	1,250	SY	PERMANENT SOIL REINFORCEMENT MAT
604200000-E	1632	40	LF	1/4" HARDWARE CLOTH
604800000-E	SP	60	SY	FLOATING TURBIDITY CURTAIN
607000000-N	SP	8	EA	SPECIAL STILLING BASINS
608400000-E	1660	3.5	ACR	SEEDING & MULCHING
608700000-E	1660	2	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	2.5	TON	FERTILIZER TOPDRESSING
611400000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
612300000-E	1670	0.25	ACR	REFORESTATION

5/28/99

02-AUG-2005 10:03
RD223226.dwg sum.dgn