

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,516 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	1.13 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	534 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	11,603 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")	8,980 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")	4,355 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	1,938 SY		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	711.6 TON		
0010	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	92 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	29,182 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,316 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,785 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	79 TON		
0015	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	36,559 SY		
0016	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	7 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	2605000000-N	SP	WHEELCHAIR RAMPS	15 EA		
001E	2830000000-N	858	ADJUSTMENT OF MANHOLES	85 EA		
001E	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	75 EA		
002C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	71,351 LF		
0021	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	136,890 LF		
0022	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	1,041 LF		
0023	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	830 LF		
0024	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	253 LF		
002E	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	219 LF		
002E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	50 LF		
0027	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,756 LF		
002E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	18 EA		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	214 EA		
003C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	350,296 LF		
0031	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	34 LF		
0032	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	26 LF		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4		
				EA		
0034	6110000000-E	SP	RESIDENTIAL SEEDING	0.55		
				ACR		
003E	7300000000-E	1715	TRENCHING (UNPAVED)	775		
				LF		
003E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	11		
				EA		
0037	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	13,600		
				LF		
003E	7456000000-E	1726	LEAD-IN CABLE	850		
				LF		

1301/Nov16/Q677053.28/D132780100000/E38

Total Amount Of Bid For Entire Project :

C201517
COUNTY: Alamance County

2/16/99

Contract No: C201517
County: Alamance

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General