

NOTES

APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE BRIDGE DECK.

THE 6"COMP. A.B.C. SHALL EXTEND 10'-0"BEYOND THE END OF THE APPROACH SLAB AND 1'-0"OUTSIDE OF EACH EDGE OF SLAB.

FOR REINFORCED BRIDGE APPROACH FILL INCLUDING FABRIC, IMPERMEABLE GEOMEMBRANE, 4" Ø DRAINAGE PIPE, #78M STONE, AND SELECT MATERIAL, SEE ROADWAY PLANS.

TEMPORARY DRAINAGE AND TEMPORARY BERM AND SLOPE DRAINS WILL BE PAID FOR UNDER THE LUMP SUM PRICE FOR BRIDGE APPROACH SLAB.

THE CONTRACTOR MAY USE 4"TYPE B-25.0B ASPHALT CONCRETE BASE COURSE IN LIEU OF 6"COMP. A.B.C. IF THIS OPTION IS USED, THE BASE COURSE SHALL EXTEND 1'-0"BEYOND THE END OF THE APPROACH SLAB AND THE WIDTH SHALL BE THE SAME AS THAT OF THE APPROACH SLAB.

AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

THE CONTRACTOR MAY USE 5"CLASS "A" CONCRETE BASE IN LIEU OF 6" COMP. A.B.C. IF THIS OPTION IS USED, THE CONCRETE BASE SHALL EXTEND 1'-0"BEYOND THE END OF THE APPROACH SLAB AND THE WIDTH SHALL BE THE SAME AS THAT OF THE APPROACH SLAB. THE CONCRETE SHALL BE FINISHED TO A SMOOTH SURFACE AND A LAYER OF 30 LB ROOFING FELT SHALL BE PLACED BETWEEN THE CONCRETE BASE AND THE APPROACH SLAB TO PREVENT BOND. THE APPROACH SLAB SHALL NOT BE CAST UNTIL THE CONCRETE BASE HAS REACHED AN AGE OF THREE CURING DAYS.

THE JOINT SHALL BE SAWED PRIOR TO THE CASTING OF THE PARAPET AND END POST.

FOR EVAZOTE JOINT SEALS, SEE SPECIAL PROVISIONS.


THE NOMINAL UNCOMPRESSED SEAL WIDTH OF THE EVAZOTE JOINT SEAL SHALL BE 2 $\frac{1}{2}$.


THE COST OF THE ELASTOMERIC CONCRETE IS INCLUDED IN THE PAY ITEM FOR "EVAZOTE JOINT SEALS."


FOR ELASTOMERIC CONCRETE, SEE SPECIAL PROVISIONS.

BILL OF MATERIAL (END BENT 2) NO. | SIZE | TYPE | LENGTH | WEIGHT #4 STR 16'-6" ***** A1 24 A2 24 | #4 | STR | 16'-5" | **∗** B1 61 | #5 | STR | 10'-7" B2 61 #6 | STR | 11'-7" 1061 REINFORCING STEEL = 1324 LBS * EPOXY COATED REINF. STEEL = 938 LBS CLASS AA CONCRETE 14.3 C.Y.

PLAN @ END BENT 2








END OF CURB WITHOUT SHOULDER BERM GUTTER

(OMIT TAPER WHEN SHOULDER BERM GUTTER IS REQUIRED)

CURB DETAILS



DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD

BRIDGE APPROACH
SLAB FOR
END BENT 2

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-25
1			3			TOTAL SHEETS
2			4,			26