

PROJECT REFERENCE NO.	SHEET NO.
38127	PM-1
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

PAVEMENT MARKING SCHEDULE

PAVEMENT MARKING LINES

AA - THERMOPLASTIC (4" WHITE, 90 MILS)	EDGE LINE
AB - THERMOPLASTIC (4" WHITE, 120 MILS)	10 FT. WHITE SKIP
AC - THERMOPLASTIC (4" WHITE, 120 MILS)	4" X 2' MINISKEP
AD - THERMOPLASTIC (4" WHITE, 120 MILS)	SOLID LANE LINE
AE - THERMOPLASTIC (4" YELLOW, 120 MILS)	DOUBLE YELLOW
AF - THERMOPLASTIC (24" WHITE, 120 MILS)	STOPBAR
AG - THERMOPLASTIC (4" YELLOW, 120 MILS)	10 FT. YELLOW SKIP
AH - THERMOPLASTIC (4" YELLOW, 120 MILS)	SINGLE YELLOW
AI - THERMOPLASTIC (8" YELLOW, 90 MILS)	YELLOW DIAGONAL

PAVEMENT MARKING SYMBOLS

BA - THERMOPLASTIC (LEFT TURN ARROW, 90 MILS)
BB - THERMOPLASTIC (RIGHT TURN ARROW, 90 MILS)
BC - THERMOPLASTIC (STRAIGHT ARROW, 90 MILS)
BD - THERMOPLASTIC (COMBO STRAIGHT/RIGHT ARROW, 90 MILS)
BE - THERMOPLASTIC (COMBO STRAIGHT/LEFT ARROW, 90 MILS)
BF - THERMOPLASTIC (COMBO STRAIGHT/RIGHT/LEFT ARROW, 90 MILS)

NOTE

EDGE LINES SHALL BE 2.0' FROM PROPOSED EP.
 PAINT MARKINGS AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES, NCDOT ROADWAY STANDARD DRAWINGS, AND THE CURRENT EDITION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). QUANTITIES FOR THESE ITEMS HAVE BEEN ACCOUNTED FOR IN THE CONTRACT BID FORM.

