

PROJECT NO.	SHEET NO.	TOTAL NO.
7CR.10791.6, ETC.	8	16

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	1 1/2" MILLING SY	3" MILLING SY	1" MILLING SY	1.25" MILLING SY	0" TO 1.25" MILLING SY	0" TO 3" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, 1 1/2" SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	PG 64-22 PLANT MIX TONS	AST MAT COAT, 78M SY	WHEELCHAIR RAMPS EA	RETROFITTING EXISTING WHEELCHAIR RAMP EA	MANHOLES EA	METER OR VALVE BOX EA	TRENCHING (UNPAVED)	PULL BOX EA	INDUCTIVE LOOP SAW CUT LF	LEAD-IN CABLE LF									
																													NO	MI	FT	TONS	SY	SY	SY	SY	SY
7CR.307918.6	Rockingham	16	US 158	FROM US 29B BRIDGE TO REIDSVILLE NCL	1	0.18	24	10		22					200	4	294		18																		
7CR.307918.6	Rockingham	17	SR 2670 (SOUTH SCALES STREET)	FROM JUST SOUTH OF TRIANGLE ROAD (NON SYSTEM) TO SANDS STREET (NON SYSTEM)	2	0.11	26	125									158		9																		
					2	0.02	24-26													21		1															
					2	0.41	24													486		29					1	5									
TOTAL FOR MAP NO. 17						0.54		125	0	0	0	0		0	0	0	665		39				1	5													
TOTAL FOR PROJ NO. 7CR.307918.6						0.72		135	0	22	0	0		200	4	959		57					1	5													
7CR 307920.6	Rockingham	18	SR 1603 (OLD 220 BUSINESSO)	FROM JOINT NORTH OF NC 770 TO STONEVILLE NCL	5	0.09	36											133		8		3	1	1	1												
					6	0.04	36													59		4	638			1	1										
					6	0.04	27-36														52		3	585			1	1									
					6	0.35	27														470		28	4,144			5	1									
					3	0.003	22-27														3		1	43													
TOTAL FOR MAP NO. 18						0.523		0	0	0	0	0	2458	0	0	0	717		44	5,410	3	1	8	3													
TOTAL FOR PROJ NO. 7CR 307920.6						0.523		0	0	0	0	0	2458	0	0	0	717		44	5,410	3	1	8	3													
7CR.307922.6	Rockingham	19	NC 770 (MEADOW ROAD)	FROM 1774 (HUNDLEY ROAD) TO EDEN NCL	5	0.87	36							7156			1,410		85				20	12	150	2	2,500	125									
7CR.307922.6	Rockingham	20	SR 1741 (CASCADE STREET)	FROM NC 770 TO EDEN NCL	3	0.01	23-29										11		1	153																	
					3	0.01	22-23													9		1	132														
					3	0.02	21-22													18		1	252														
TOTAL FOR MAP NO. 20						0.04		0	0	0	0	0	0	0	0	0	38		3	537			0														
7CR.307922.6	Rockingham	21	SR 1737 MAIN (STREET)	FROM NC 770 TO EDEN NCL	5	0.05	36						762				74		4																		
					2	0.01	24-36													12		1															
					2	0.01	20-24														9		1														
TOTAL FOR MAP NO. 21						0.07		0	0	0	0	762	0	0	0	95		6	0				0														
7CR.307922.6	Rockingham	22	SR 1797 (FRIENDLY ROAD)	FROM SR 1714 (SUMMIT ROAD) TO EDEN NCL	7	0.03	31-40	5									53		3																		
					8	0.01	29.5-31													15		1					1										
					1	0.01	24-27.5														13		1														
					8	0.01	23-24														12		1														
					1	0.01	23														12		1														
TOTAL FOR MAP NO. 22						0.07		5	0	0	0	0	288	0	0	105		7	0				1														
TOTAL FOR PROJ NO. 7CR.307922.6						1.05		5	0	0	0	0	762	7444	0	0	1,648		101	537			21	12	150	2	2,500	125									
GRAND TOTAL						29.53		2,775	884	89	48	137	3,220	7,444	3,070	15	30,616	2,682	2,019	64,238	3	1	41	47	150	2	2,500	125									