PROJECT NO.	SHEET NO.	TOTAL NO.
7CR.10791.6, ETC.	6	16

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	1½" MILLING SY	3" MILLING SY	1" MILLING	1.25" MILLING SY	0" TO 1.25" MILLING SY	0" TO 3" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	PG 64-22 PLANT MIX TONS	AST MAT COAT, 78M SY	WHEELCHAIR RAMPS EA	RETROFITTING EXISTING WHEELCHAIR RAMP EA	MANHOLES EA	METER OR VALVE BOX EA	TRENCHING (UNPAVED)	PULL BOX EA	INDUCTIVE LOOP SAW CUT LF	LEAD-IN CABLE LF
7CR.20791.6	Rockingham	4	SR 2598 (COOK FLORIST ROAD)	FROM JOINT JUST SOUTH OF NC 87 TO SR 2600 (MIZPAH ROAD)	2	1.23	21	230									1,066		64									
					2	0.01	24										10		1									
					2	0.59	21-22										523		31									
					2	0.01	22-27										10		1									
					2	0.01	27-37										13		1									
TOTAL FOR MAP NO. 4						1.85		230		0						0	1,622		98									
7CR.20791.6	Rockingham	5	SR 2670 (NORTH SCALES STREET)	REIDSVILLE NCL TO NC 14	1	0.01	25-28	25							213		13		1									
					1	0.49	25										727		44									
					1	0.06	33										158		10									
					1	0.03	33-40										54		3									
					1	0.04	40-57										96		6									
TOTAL FOR MAP NO. 5						0.63		25		0					213	0	1,048		64									
7CR.20791.6	Rockingham	6	SR 1797 (FRIENDLY ROAD)	FROM EDEN NCL TO THE VIRGINIA STATE LINE	1	0.38	23-24										479		29				2	3				
					1	0.17	23-25										242		15									
					1	0.19	25										235		14					1				
					1	0.37	24-25										489		29				2	3				
TOTAL FOR MAP NO. 6						1.11		0		0					0	0	1,445		87				4	7				
7CR.20791.6	Rockingham	7	SR 1741 (CASCADE STREET)	FROM EDEN NCL TO THE VIRGINIA STATE LINE	3	0.05	21	265									49		3	616								
					3	0.04	26										43		3	610								
					3	0.82	22										764		46	10,584								
					3	0.03	22-26										30		2	422								
					3	0.08	19-26										63		4	892								
					3	0.04	19-21										33		2	469								
					3	0.37	19										290		17	4,124								
TOTAL FOR MAP NO. 7						1.43		265		0					0	0	1,272		77	17,717								
7CR.20791.6	Rockingham	8	SR 1700 (FISHER HILL ROAD)	FROM NC 14 BRIDGE TO THE VIRGINIA STATE LINE	4	0.01	30											28	2									
					4	0.03	18-21											59	4									
					4	0.7	18.5											420	27									
					4	0.01	23											8	1									
					4	0.06	18.5											36	1									
TOTAL FOR MAP NO. 8						0.81		0		0					0	0	0	551	35	0								
7CR.20791.6	Rockingham	9	SR 1603 (OLD US 220)	FROM STONEVILLE NCL TO JUST NORTH OF SR 1360 (SMITH ROAD	9	2.25	22				48				732			1,673	109	29,040								
7CR.20791.6	Rockingham	10	SR 2150 (RIVER ROAD)	FROM SR 2145 (SETTLE BRIDGE ROAD TO SR 2153 (GROGAN ROAD)	2	1.25	19	145				137			1294		1,156		69									
					2	1.06	19-20										873		52									
					2	0.07	22-27										71		4									
					2	0.02	27										22		1									
					2	0.01	27-30										12		1									
					2	0.04	22-30										43		3									
					2	1.64	20										1,374		82									
TOTAL FOR MAP NO. 10						4.09		145		0	0	137			1294	0	3,551	0	212									
7CR.20791.6	Rockingham	11	SR 2265 (DEERWOOD LANE)	FROM END OF PAVEMENT TO CUL DE SAC	4	0.59	20	20										458	27									