

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	324,315 SY		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	4,592 SY		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	47,488 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4-1/2")	422 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	1,566 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")	4,133 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 2")	7,470 SY		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (3" TO 4-1/2")	4,500 SY		
0010	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	769.26 TON		
0011	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	8,434 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,671.78 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	576 TON		
0015	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	2,628 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0016	1704000000-E	SP	PATCHING EXISTING PAVEMENT	228 TON		
0017	1840000000-E	665	MILLED RUMBLE STRIPS	102,000 LF		
0018	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S9.5D	43,840 TON		
0019	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0020	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	682 SF		
0021	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	288 SF		
0022	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0023	4420000000-N	1120	CHANGEABLE MESSAGE SIGNS	3 EA		
0024	4430000000-N	1130	DRUMS	600 EA		
0025	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	3 EA		
0026	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	110,844 LF		
0027	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	41,433 LF		
0028	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,622 LF		
0029	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	6,812 LF		
0030	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	189 LF		
0031	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	41 EA		
0032	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	304,554 LF		
0033	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	3,244 LF		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	13,624 LF		
0035	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	378 LF		
0036	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	82 EA		
0037	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	100 LF		
0038	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	100 LF		
0039	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	4 EA		
0040	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,309 EA		
0041	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0812/Jan13/Q1042592.04/D131585200000/E41			Total Amount Of Bid For Entire Project :			

C201261 (I-4713)  
COUNTY: ALAMANCE

2/16/99

Contract No: C201261  
County: Alamance

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General