

(wire push-button and lamp as shown below)



IMPORTANT!


MAKE SURE AC ISOLATOR INSERTED IN JI4L IS SET FOR INVERTED INPUT.



LAMP NOTES

IN ORDER FOR PILOT LAMP IN FIRE HOUSE TO FUNCTION, MAKE THE FOLLOWING PROGRAMMING CHANGES TO OUTPUT NO. 33.

- 1. CHANGE THE FUNCTION OF C1 PIN 35 TO BE AN OUTPUT FOR PREEMPT 2. THIS IS ACCOMPLISHED BY THE FOLLOWING:
 - A) FROM MAIN MENU SELECT 6 (OUTPUTS). THEN SELECT 1 (OUTPUT ASSIGNMENTS).
 - B) SCROLL TO C1 PIN 35, OUTPUT NO. 33. YOU WILL SEE THAT IT IS NOT ENABLED.
 - C) SCROLL DOWN TO PREEMPT AND INPUT "YES".
 YOU WILL THEN BE ASKED FOR A PREEMPT NO.
 ENTER A "2" HERE.
 - D) THE OUTPUT IS NOW ASSIGNED FOR PRE-2 OUTPUT.
- 2. IF TERMINAL 114 HAS A CONFLICT MONITOR WIRE CONNECTED, REMOVE, TAPE AND LABEL WIRE.
- 3. MAKE SURE LOAD RESISTORS ARE IN PLACE AS SHOWN IN LOAD RESISTOR INSTALLATION DETAIL.
- 4. INSERT LOADSWITCH FOR S2P.




PROGRAMING LOGICAL I/O PROCESSOR DETAIL

NOTE

WHEN PREEMPT DELAY TIMER IS IN USE STEP 1 SHOWN BELOW IS NECESSARY TO ENSURE PILOT LAMP IN FIRE HOUSE WILL ACTIVATE IMMEDIATELY AFTER PUSH BUTTON IS DEPRESSED:

STEP 1

FROM MAIN MENU: ENTER (6) (OUTPUTS).
THEN SELECT (3) (LOGICAL I/O PROCESSOR).




STEP 2

NOTE

IN ORDER FOR PILOT LAMP IN FIRE HOUSE TO DEACTIVATE IMMEDIATELY AFTER ENDING PREEMPTION, PROGRAM THE FOLLOWING:

TOGGLE THE + BUTTON ONCE TO ACCESS LOGICAL I/O COMMAND *2.



STEP 3

FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN "1" (PHASE CONTROL FUNCTIONS).

SCROLL TO THE BOTTOM OF THE MENU AND ENABLE LOGICAL PROCESSOR (ACT LOGIC 1-16)

BY FLAGGING #1 AND #2.

END OF PROGRAM.

PLANS PREPARED BY:
RUMMEL KLEPPER & KAHL, LLP

consulting engineers
5800 FARINGDON PLACE SUITE 105
RALEIGH, NORTH CAROLINA 27609-3960

DIVISION OF HIGHWAYS

EMERGENCY VEHICLE PREEMPTION PROGRAMMING DETAIL

PROJECT REFERENCE NO.

R-2813C

SIG.49

(program controller as shown below)

FROM MAIN MENU PRESS 'A' (PREEMPTION), THEN '1' (STANDARD PREEMPTIONS). PRESS THE "NEXT" KEY TO ADVANCE TO PREEMPT 2.

PREEMPTION #2 SETTINGS (NEXT:1-10) INTERVAL/TIMING CLEAR/DWELL PHASES GRN YEL RED 12345678910111213141516 1 255 0.0 0.0 X 2 0 0.0 0.0 3 0 0.0 0.0 4 0 0.0 0.0 5 0 0.0 0.0
EXIT CALLS !
OPTIONS
PRIORITY (Y/N TO SELECT)MED
DELAY TIMER (0-255 SEC)*
MIN GREEN BEFORE PRE (O= DEFAULT)1
,
PED CLEAR BEFORE PRE (O= DEFAULT)12
YELLOW CLEAR BEFORE PRE (0= DEFAULT).4.7
RED CLEAR BEFORE PRE (O= DEFAULT)3.0
DWELL MIN TIMER (0-255 SEC)*
DWELL MAX TIMER (0=OFF,1-255MIN)0
DWELL HOLD-OVER TIMER (0-255)0
LATCH CALL?Y
LINK TO NEXT PREEMPT?N
ENABLE BACKUP PROTECTION?N
HOLD CLEAR 1 PHASES DURING DELAY?Y
FAST GREEN FLASH DWELL PHASES?N
PED CLEARANCE THROUGH YELLOW?N
INHIBIT OVERLAP GREEN EXTENSION?N
SERVICE DURING SOFTWARE FLASH?Y
REST IN RED DURING DWELL INTERVAL?N
FLASH DWELL INTERVAL?N
ALLOW PEDS IN DWELL INTERVAL?N
RE-TIME DWELL INTERVAL?Y
OVERLAPS: ABCDEFGHIJKLMNOF
DWELL INT FLASH YELLOW
1
OMIT OVERLAPS:

* DENOTES TIMING TO BE DETERMINED IN FIELD.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 13-0284 DESIGNED: 02/15/2003 SEALED: 02/26/2004 REVISED: TBD

SIGNAL UPGRADE - FINAL PAGE 2 OF 2

Prepared for the Offices of: Prepared for the Offices of: Prepared for the Offices of: OF TRANSPORTATION OF TRANSPORT

US 25 (HENDERSONVILLE ROAD) AT

NC 146 (LONG SHOALS ROAD)

DIVISION 13

BUNCOMBE COUNTY

PLAN DATE:

JULY 2003

REVIEWED BY:

DEVICIONS

REVIEWED BY:

ASHEVILE

PROPRIED BY:

N W YALCH

REVIEWED BY:

DEVICIONS

