

# EMERGENCY VEH. PREEMPTION PUSHBUTTON AND INDICATOR LAMP WIRING DETAIL

(wire push-button and lamp as shown below)



## IMPORTANT!

MAKE SURE AC ISOLATOR INSERTED IN JI4L IS SET FOR INVERTED INPUT.



### LAMP NOTES

IN ORDER FOR PILOT LAMP IN FIRE HOUSE TO FUNCTION, MAKE THE FOLLOWING PROGRAMMING CHANGES TO OUTPUT NO. 33.

- 1. CHANGE THE FUNCTION OF C1 PIN 35 TO BE AN OUTPUT FOR PREEMPT 2. THIS IS ACCOMPLISHED BY THE FOLLOWING:
  - A) FROM MAIN MENU SELECT 6 (OUTPUTS). THEN SELECT 1 (OUTPUT ASSIGNMENTS).
  - B) SCROLL TO C1 PIN 35, OUTPUT NO. 33. YOU WILL SEE THAT IT IS NOT ENABLED.
  - C) SCROLL DOWN TO PREEMPT AND INPUT "YES".
    YOU WILL THEN BE ASKED FOR A PREEMPT NO.
    ENTER A "2" HERE.
  - D) THE OUTPUT IS NOW ASSIGNED FOR PRE-2 OUTPUT.
- 2. IF TERMINAL 114 HAS A CONFLICT MONITOR WIRE CONNECTED, REMOVE, TAPE AND LABEL WIRE.
- 3. MAKE SURE LOAD RESISTORS ARE IN PLACE AS SHOWN IN LOAD RESISTOR INSTALLATION DETAIL ON PAGE 1.
- 4. INSERT LOADSWITCH FOR S2P.


## PROGRAMING LOGICAL I/O PROCESSOR DETAIL

#### NOTE

WHEN PREEMPT DELAY TIMER IS IN USE STEP 1 SHOWN BELOW IS NECESSARY TO ENSURE PILOT LAMP IN FIRE HOUSE WILL ACTIVATE IMMEDIATELY AFTER PUSH BUTTON IS DEPRESSED:

#### STEP 1

FROM MAIN MENU: ENTER (6) (OUTPUTS).
THEN SELECT (3) (LOGICAL I/O PROCESSOR).




#### STEP 2

### NOTE

IN ORDER FOR PILOT LAMP IN FIRE HOUSE TO DEACTIVATE IMMEDIATELY AFTER ENDING PREEMPTION, PROGRAM THE FOLLOWING:

TOGGLE THE + BUTTON ONCE TO ACCESS LOGICAL I/O COMMAND \*2.



#### STEP 3

FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN "1" (PHASE CONTROL FUNCTIONS).

SCROLL TO THE BOTTOM OF THE MENU AND ENABLE LOGICAL PROCESSOR (ACT LOGIC 1-16)

BY FLAGGING #1 AND #2.

END OF PROGRAM.



#### PLANS PREPARED BY:

RUMMEL KLEPPER & KAHL, LLP

consulting engineers

5800 FARINGDON PLACE SUITE 105

RALEIGH, NORTH CAROLINA 27609-3960

DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
R-2813C	SIG.46

# EMERGENCY VEHICLE PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)

FROM MAIN MENU PRESS 'A' (PREEMPTION), THEN '1' (STANDARD PREEMPTIONS), PRESS THE "NEXT" KEY TO ADVANCE TO PREEMPT 2,

_	
	PREEMPTION #2 SETTINGS (NEXT:1-10) INTERVAL/TIMING   CLEAR/DWELL PHASES GRN YEL RED   12345678910111213141516 1 255 0.0 0.0   X 2 0 0.0 0.0   3 0 0.0 0.0   4 0 0.0 0.0   5 0 0.0 0.0
- 1	EXIT CALLS
1	EXII CALLS
1	OPTIONS
ı	
I	PRIORITY (Y/N TO SELECT)MED
	DELAY TIMER (0-255 SEC)*
	MIN GREEN BEFORE PRE (O= DEFAULT)1
l	
	PED CLEAR BEFORE PRE (O= DEFAULT)O
	YELLOW CLEAR BEFORE PRE (O= DEFAULT).4.7
l	RED CLEAR BEFORE PRE (O= DEFAULT)3.0
ŀ	DWELL MIN TIMER (0-255 SEC)*
l	
	DWELL MAX TIMER (0=OFF,1-255MIN)0
	DWELL HOLD-OVER TIMER (0-255)
l	LATCH CALL?Y
l	LINK TO NEXT PREEMPT?N
l	ENABLE BACKUP PROTECTION?N
l	HOLD CLEAR 1 PHASES DURING DELAY?Y
	FAST GREEN FLASH DWELL PHASES?N
	PED CLEARANCE THROUGH YELLOW?N
	INHIBIT OVERLAP GREEN EXTENSION?N
	SERVICE DURING SOFTWARE FLASH?Y
	REST IN RED DURING DWELL INTERVAL?N
	FLASH DWELL INTERVAL?N
	ALLOW PEDS IN DWELL INTERVAL?N
	RE-TIME DWELL INTERVAL?Y
	OVERLAPS:   ABCDEFGHIJKLMNOP
	DWELL INT FLASH YELLOW !
	OMIT OVERLAPS:
	OWIT OVERLAND.
ı	

\* DENOTES TIMING TO BE DETERMINED IN FIELD.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 13-0284T2 DESIGNED: 04/14/2003 SEALED: 02/26/2004 REVISED: TBD

TEMPORARY SIGNAL 2 - PHASE II - TCP 29
PAGE 2 OF 2

Prepared for the Offices of:

NC 146 (LONG SHOALS ROAD)

DIVISION 13

BUNCOMBE COUNTY

ASHEVI

PLAN DATE: JULY 2003

REVIEWED BY: J O DEATON

NC 146 (LONG SHOALS ROAD)

DIVISION 13 BUNCOMBE COUNTY ASHEVILLE

PLAN DATE: JULY 2003 REVIEWED BY: J O DEATON

PREPARED BY: M W YALCH REVIEWED BY:

REVISIONS INIT. DATE

SIGNATURE DATE

SIG. INVENTORY NO. 13-0284T2

SEAL