

**STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
CROSS-SECTION SUMMARY**

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

DETOUR CONSTRUCTION BEFORE BRIDGE			MAIN LINE -L- CONSTRUCTION AFTER BRIDGE		
Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)	L	(cu. yd.)	(cu. yd.)
14+00.000	0	0	22+00.000	7	56
14+50.000	4	1	22+50.000	14	60
15+00.000	6	18	23+00.000	45	41
15+50.000	7	66	23+50.000	109	13
16+00.000	5	151	24+00.000	77	1
16+50.000	0	287	DETOUR REMOVAL BEFORE BRIDGE		
17+00.000	0	404	Station	Uncl. Exc.	Embt
17+50.000	0	462	L	(cu. yd.)	(cu. yd.)
18+00.000	0	491	14+00.000	0	0
18+50.000	0	529	14+50.000	5	0
19+00.000	0	620	15+00.000	24	0
19+50.000	0	661	15+50.000	89	0
20+00.000	0	618	16+00.000	184	0
20+39.660	0	510	16+50.000	300	0
DETOUR CONSTRUCTION AFTER BRIDGE			17+00.000	414	0
Station	Uncl. Exc.	Embt	17+50.000	483	0
L	(cu. yd.)	(cu. yd.)	18+00.000	524	0
21+30.090	0	0	18+50.000	542	0
21+50.000	0	150	19+00.000	589	0
22+00.000	0	1061	19+50.000	621	0
22+50.000	0	964	20+00.000	593	0
23+00.000	0	688	20+39.660	461	0
23+50.000	0	365	DETOUR REMOVAL AFTER BRIDGE		
24+00.000	0	163	Station	Uncl. Exc.	Embt
24+50.000	15	87	L	(cu. yd.)	(cu. yd.)
25+00.000	18	67	21+30.090	0	0
25+50.000	20	35	21+50.000	393	0
26+00.000	35	5	22+00.000	975	0
26+50.000	51	1	22+50.000	915	0
27+00.000	50	1	23+00.000	675	0
27+50.000	44	1	23+50.000	361	0
28+00.000	36	0	24+00.000	168	0
28+50.000	31	0	24+50.000	86	
29+00.000	14	0	25+00.000	66	0
MAIN LINE -L- CONSTRUCTION BEFORE BRIDGE			25+50.000	32	7
Station	Uncl. Exc.	Embt	26+00.000	3	32
L	(cu. yd.)	(cu. yd.)	26+50.000	1	51
15+00.000	0	0	27+00.000	1	50
15+50.000	39	16	27+50.000	1	44
16+00.000	43	37	28+00.000	0	36
16+50.000	37	39	28+50.000	0	31
17+00.000	59	78			
17+50.000	51	145			
18+00.000	51	200			
18+50.000	57	189			
19+00.000	60	136			
19+50.000	74	155			
20+00.000	92	124			
20+43.000	106	54			
MAIN LINE -L- CONSTRUCTION AFTER BRIDGE					
Station	Uncl. Exc.	Embt			
L	(cu. yd.)	(cu. yd.)			
21+43.000	0	0			
21+50.000	2	7			