PROJECT REFERENCE NO.	SHEET NO.
U-2913B	EC-6/CONST.7
R /W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
CONST.REV.	
R /W REV.	

METRIC

2.5 0 5

NOTE:
PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE- B AND TEMPORARY ROCK SILT CHECKS TYPE-A AT DRAINAGE OUTLETS.

CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 7

-L-
PI Sta 54+23.225
Δ = 7° 40' 19.3" (LT)
L = 120.512
T = 60.346
R = 900.000
SE = SEE PLANS

JAMESTOWN PRESBYTERIAN CHURCH
DB 3450 PG 2235
4.031 Ha (DEED)
7

CHURCH OF GOD OF PROPHECY
DB 2849 PG 565
8.611 Ha (DEED)
3

CHM & S a N.C. PARTNERSHIP
DB 3821 PG 1933
1.220 Ha (DEED)
6

LEE & STEPHANIE PARDUE
DB 3608 PG 720
9956 SM (DEED)
8

GREENWOOD & CHARLES, INC.
DB 3533 PG
8.138 Ha (DEED)
9

NAD 83

DETAIL F
SPECIAL SHOULDER
EXIST GROUND
4:1
0.0833
SEE CROSS SECTIONS FOR SLOPE
DRAINAGE STRUCTURE
-L- STA 54+70 LT - STA 55+60 LT

DETAIL I
STANDARD BASE DITCH
(Not to Scale)
Natural Ground
2:1
D
d
B
Min. D = 0.3 m
Max. d = 0.3 m
B = 0.9 m
Type of Liner = PERMANENT SOIL REINFORCEMENT MAT

-L- 53+30 LT
42m @ 3.84%
DDE = 60 m3

MATCH-LINE -L- STA 53+20 SEE SHEET 6

MATCH-LINE -L- STA 54+80 SEE SHEET 8

-L- PCSta.53+62.879

MONOLITHIC ISLAND

SEE SHEET 25 FOR -L- PROFILE