

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

# SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200862

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	4025000000-E	901	39	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	6087000000-E	1660	1	ACR	MOWING
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	4072000000-E	903	82	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
0043000000-N	226	Lump Sum		GRADING	4102000000-N	904	6	EA	SIGN ERECTION, TYPE E	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	4155000000-N	907	8	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
0057000000-E	226	50	CY	UNDERCUT EXCAVATION	4412000000-E	SP	399	SF	WORK ZONE SIGNS (STATIONARY)	6108000000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
0318000000-E	300	8	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	4412100000-E	SP	144	SF	WORK ZONE SIGNS (PORTABLE)	611000000-E	SP	100	LF	IMPERVIOUS DIKE
0343000000-E	310	48	LF	15" SIDE DRAIN PIPE	4412200000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6114000000-N	SP	1	HR	SPECIALIZED HAND MOWING
0366000000-E	310	20	LF	15" RC PIPE CULVERTS, CLASS III	4430000000-N	1130	30	EA	DRUMS	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
1220000000-E	545	100	TON	INCIDENTAL STONE BASE	4435000000-N	1135	30	EA	CONES	6123000000-E	1670	0.1	ACR	REFORESTATION
1489000000-E	610	270	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4446100000-E	SP	88	LF	BARRICADES (TYPE III)					
1525000000-E	SP	390	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	4455000000-N	1150	33	MD	FLAGGER					
1560000000-E	620	37	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4460000000-N	1155	3	EA	WARNING LIGHTS (TYPE B)					
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES	4810000000-E	1205	9,788	LF	PAINT PAVEMENT MARKING LINES (4")					
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29	6000000000-E	1605	160	LF	TEMPORARY SILT FENCE					
2556000000-E	846	12	LF	SHOULDER BERM GUTTER	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A					
3030000000-E	862	50	LF	STEEL BM GUARDRAIL	6009000000-E	1610	250	TON	STONE FOR EROSION CONTROL, CLASS B					
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6012000000-E	1610	320	TON	SEDIMENT CONTROL STONE					
3165000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (SKT TL-2)	6015000000-E	1615	1	ACR	TEMPORARY MULCHING					
3180000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77 SHOP CURVED)	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING					
3270000000-N	SP	1	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING					
3317000000-N	862	3	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77	6029000000-E	SP	550	LF	SAFETY FENCE					
3649000000-E	876	2	TON	PLAIN RIP RAP, CLASS B	6030000000-E	1630	350	CY	SILT EXCAVATION					
3656000000-E	876	202	SY	FILTER FABRIC FOR DRAINAGE	6036000000-E	1631	520	SY	MATTING FOR EROSION CONTROL					
					6042000000-E	1632	770	LF	1/4" HARDWARE CLOTH					
					6070000000-N	SP	1	EA	SPECIAL STILLING BASINS					
					6084000000-E	1660	1	ACR	SEEDING & MULCHING					

5/28/99

25-OCT-2004 14:58  
PS:\bill\calaw...  
B3659.sum