

**PROJECT SPECIAL PROVISIONS**

Roadway

7-1-95

SP1R01

**CLEARING AND GRUBBING:**

9-17-02

Perform clearing on this project to the limits established by Method "II" shown on Standard No. 200.02 of the Roadway Standards.

The 2002 Standard Specifications shall be revised as follows:

Page 2-3, Article 200-5

Delete the first sentence of this article and insert the following:

The property owner will have no right to use or reserve for his use any timber on the project. All timber cut during the clearing operations is to become the property of the Contractor, and shall be either removed from the project by him, or else shall be satisfactorily disposed of as hereinafter provided.

SP2R01

**BORROW EXCAVATION:**

2-19-02

Revise the 2002 Standard Specifications as follows:

Page 2-20, Article 230-6

After the first paragraph, insert the following paragraph:

"No direct payment will be made for the work of Evaluation of Potential Wetlands and Endangered Species as outlined above. Payment at the contract unit price for the pay item 'Borrow Excavation' or 'Grading - Lump Sum' will be considered full compensation for this work.'

SP2R37

**SHOULDER AND FILL SLOPE MATERIAL(LUMP SUM GRADING)**

5-21-02

**General:**

Perform the required shoulder and slope construction for this project in accordance with the applicable requirements of Section 226 of the Standard Specifications except as follows:

Construct the top 6 inches (150 mm) of shoulder and fill slopes with soils capable of supporting vegetation.

Provide soil with a P.I. greater than 6 and less than 25 and with a pH ranging from 5.5 to 6.8. Remove stones and other foreign material 2 inches (50 mm) or larger in diameter. All soil is subject to test and acceptance or rejection by the Engineer.

Obtain material from within the project limits or approved borrow source.

**Compensation:**

No direct payment will be made for this work, as the cost of this work will be considered to be a part of the work being paid for at the contract lump sum price for "Grading".

SP2R45

**ASPHALT PAVEMENTS - SUPERPAVE**

**01-18-05**

Revise the 2002 *Standard Specifications* as follows:

PRIME COAT

Page 6-2, **Article 600-9**

Delete the first paragraph and substitute the following:

The quantity of prime coat to be paid will be the number of gallons (liters) of prime coat material that has been satisfactorily placed on the roadway. Each distributor load of prime coat material delivered and utilized on the project will be measured.

ASPHALT TACK COAT

Page 6-4, **Article 605-8**

Insert the following after paragraph one.

Take necessary precautions to limit the tracking and/or accumulation of tack coat material on either existing or newly constructed pavements. Excessive accumulation of tack may require corrective measures.

FIELD VERIFICATION AND JOB MIX FORMULA ADJUSTMENTS

Page 6-7, **Article 609-4**

Delete the first paragraph and substitute the following:

Conduct field verification of the mix at each plant within 30 calendar days prior to initial production of each mix design, when required by the Allowable Mix Adjustment Policy and when directed as deemed necessary.

Page 6-8, **Article 609-4**

Delete the first paragraph and substitute the following:

Retain records of these calibrations and mix verification tests, including Superpave Gyratory Compactor (SGC) printouts, at the QC laboratory. In addition, furnish copies, including SGC printouts, to the Engineer for review and approval within one working day after beginning production of the mix.

Page 6-8, **Article 609-4**

Add the following sentence at the end of the last paragraph:

Any mix produced that is not verified may be assessed a price reduction at the Engineer's discretion in addition to any reduction in pay due to mix and/or density deficiencies.

Quality control minimum sampling and testing schedule:

Page 6-8, **Subarticle 609-5(A)**

Delete the second sentence in the fourth paragraph and substitute the following:

This person is responsible for monitoring all roadway paving operations and all quality control processes and activities, to include stopping production or implementing corrective measures when warranted.

Page 6-9, **Subarticle 609-5(C)1**

Delete the second sentence in the second paragraph and substitute the following:

Retain the QC compacted volumetric test specimens for 5 calendar days, commencing the day the specimens are prepared.

**Page 6-9, Subarticle 609-5(C)2**

At the bottom of this page, delete the sentence directly above the Accumulative Production Increment and substitute the following:

Sample and test the completed mixture from each mix design at the following minimum frequency during mix production:

**Page 6-10, Subarticle 609-5(C)2**

Revise Items B, C, D and E on this page as follows:

- B. Gradation on Recovered Blended Aggregate from Mix Sample (AASHTO T 30 Modified) Grade on all sieves specified on JMF
- C. Maximum Specific Gravity (AASHTO T 209 or ASTM D 2041), optional (ASTM D 6857)
- D. Bulk Specific Gravity of Compacted Specimens (AASHTO T166), optional (ASTM D 6752), Average of 3 specimens at  $N_{des}$  gyrations (AASHTO T 312)
- E. Air Voids (VTM) (AASHTO T 269), Average of 3 specimens at  $N_{des}$  gyrations

**Page 6-11, Subarticle 609-5(C)2**

At the top of this page, delete Item B.,” Reclaimed Asphalt Pavement...” and substitute the following:

- B. Reclaimed Asphalt Pavement (RAP) Binder Content and Gradation (AASHTO T 308 Modified or T 164 and AASHTO T 30 Modified) (sampled from stockpiles or cold feed system at beginning of production and weekly thereafter). Have RAP approved for use in accordance with Article 1012-1(G). (Split Sample Required)

**Page 6-11, Subarticle 609-5(C)2**

Insert the following sampling and testing at the end of this Subarticle:

- F. Uncompacted Void Content of Fine Aggregate, AASHTO T 304, Method A (natural sand only). Performed at Mix Design and when directed as deemed necessary. (Split Sample Required)
- G. Reclaimed Asphalt Shingle Material (RAS) Binder Content and Gradation (AASHTO T 308 Modified or T 164 and AASHTO T 30 Modified) (sampled from stockpiles or cold feed system at beginning of production and weekly thereafter). Have RAS approved for use in accordance with Article 1012-1(F). (Split Sample Required)

## CONTROL CHARTS

Page 6-11, **Subarticle 609-5(C)3**

Delete the first paragraph and substitute the following:

Maintain standardized control charts furnished by the Department at the field laboratory. For mix incorporated into the project, record full test series data from all regularly scheduled random samples or directed samples which replace regularly scheduled random samples, on control charts the same day the tests are obtained.

In addition, partial test series results obtained due to reasons outlined in Subarticle 609-5(C)2 will be reported to Quality Assurance personnel on the proper forms, but will not be plotted on the control charts.

Page 6-12, **Subarticle 609-5(C)3**

Delete item 3 in the list below the second full paragraph and substitute the following:

3. If failure to stop production after two consecutive moving averages exceed the warning limits occurs, but production does stop at a subsequent time, re-establish a new moving average beginning at the actual production stop point.

Page 6-11, **Subarticle 609-5(C)2**

At the top of this page, delete Item B.,” Reclaimed Asphalt Pavement...” and substitute the following:

- B. Reclaimed Asphalt Pavement (RAP) Binder Content and Gradation (AASHTO T 308 Modified or T 164 and AASHTO T 30 Modified) (sampled from stockpiles or cold feed system at beginning of production and weekly thereafter). Have RAP approved for use in accordance with Article 1012-1(G). (Split Sample Required)

Page 6-11, **Subarticle 609-5(C)2**

Insert the following sampling and testing at the end of this Subarticle:

- F. Uncompacted Void Content of Fine Aggregate, AASHTO T 304, Method A (natural sand only). Performed at Mix Design and when directed as deemed necessary. (Split Sample Required)
- G. Reclaimed Asphalt Shingle Material (RAS) Binder Content and Gradation (AASHTO T 308 Modified or T 164 and AASHTO T 30 Modified) (sampled from stockpiles or cold feed system at beginning of production and weekly thereafter). Have RAS approved for use in accordance with Article 1012-1(F). (Split Sample Required)

## CONTROL CHARTS

Page 6-11, **Subarticle 609-5(C)3**

Delete the first paragraph and substitute the following:

Maintain standardized control charts furnished by the Department at the field laboratory. For mix incorporated into the project, record full test series data from all regularly scheduled random samples or directed samples which replace regularly scheduled random samples, on control charts the same day the tests are obtained.

In addition, partial test series results obtained due to reasons outlined in Subarticle 609-5(C)2 will be reported to Quality Assurance personnel on the proper forms, but will not be plotted on the control charts.

Page 6-12, **Subarticle 609-5(C)3**

Delete item 3 in the list below the second full paragraph and substitute the following:

- 3. If failure to stop production after two consecutive moving averages exceed the warning limits occurs, but production does stop at a subsequent time, re-establish a new moving average beginning at the actual production stop point.

Page 6-12, **Subarticle 609-5(C)3**

Delete the first and second sentence in the third full paragraph and substitute the following:

In addition, re-establish the moving averages for all mix properties.

**CONTROL LIMITS**

Page 6-12, **Subarticle 609-5(C) 4**

At the bottom of this page, delete the table and substitute the following:

**CONTROL LIMITS**

Mix Control Criteria	Target Source	Warning Limit	Moving Average Limit	Individual Limit
2.36mm Sieve	JMF	±4.0 %	±5.0 %	±8.0 %
0.075mm Sieve	JMF	±1.5 %	±2.0 %	±2.5 %
Binder Content	JMF	±0.3 %	±0.5 %	±0.7 %
VTM @ N <sub>des</sub>	JMF	±1.0 %	±1.5 %	±2.0 %
VMA @ N <sub>des</sub>	Min. Spec. Limit	-0.5%	-0.8%	-1.0%
P <sub>0.075</sub> / P <sub>be</sub> Ratio	Max. Spec. Limit	0.0	N/A	+0.4%
%G <sub>mm</sub> @ N <sub>ini</sub>	Max. Spec. Limit	N/A	N/A	+2.0%
TSR	Min. Spec. Limit	N/A	N/A	-15.0%

Allowable Retesting for Mix Deficiencies:

Page 6-14, **Subarticle 609-5C(7)**

In the first paragraph, insert the following as the fourth sentence:

The Contractor under the supervision of the Department’s QA personnel will perform these retests.

**FIELD COMPACTION QUALITY CONTROL**

Page 6-15, **Subarticle 609-5(D)1**

Delete the first and second sentences in the fourth paragraph and substitute the following:

Base and intermediate mix types (surface mixes not included) utilized for pavement widening of less than 4.0 feet and all mix types used in tapers, irregular areas and intersections (excluding full width travel lanes of uniform thickness), will not be subject to the sampling and testing frequency specified above provided the pavement is compacted using approved equipment and procedures. However, the Engineer may require occasional density sampling and testing to evaluate the compaction process.



Page 6-16, **Subarticle 609-5(D)1**

Delete item number 2 at the top of this page. Item number 3 should be re-numbered as 2 after the specified deletion.

Pavement Samples (Cores)

Page 6-16, **Subarticle 609-5(D)2**

In the first paragraph, delete the second sentence and insert the following as the last sentence in that paragraph:

The use of a separator medium beneath the layer to be tested is prohibited.

**LIMITED PRODUCTION PROCEDURE**Page 6-17, **Subarticle 609-5(D) 5**

Delete the first paragraph and substitute the following:

Proceed on limited production when, for the same mix type, one of the following items occur:

- (1) Two consecutive failing lots, excluding lots representing an individual resurfacing map or portion thereof.
- (2) Three consecutive failing lots, with each lot representing an individual resurfacing map or portion thereof.
- (3) Two consecutive failing nuclear control strips.

Pavement within each construction category (New and Other), as defined in Article 610-13, and pavement placed simultaneously by multiple paving crews will be evaluated independently for limited production purposes.

Delete the first sentence in the last paragraph and substitute the following:

If the Contractor does not operate by the limited production procedures as specified above, the two consecutive failing density lots, three consecutive failing lots with each lot representing an individual resurfacing map or portion thereof, or two consecutive failing nuclear control strips, whichever is applicable, and all mix produced thereafter will be considered unacceptable.

**DOCUMENTATION (RECORDS)**Page 6-18, **Subarticle 609-5(E)**

Delete the third and fourth sentence in the first full paragraph and substitute the following:

Maintain all QC records, forms and equipment calibrations for a minimum of 3 years from their completion date.

Delete the second full paragraph and substitute the following:

Falsification of test results, documentation of observations, records of inspection, adjustments to the process, discarding of samples and/or test results, or any other deliberate misrepresentation of the facts will result in the revocation of the applicable person's QMS certification. The Engineer will determine acceptability of the mix and/or pavement represented by the falsified results or documentation. If the mix and/or pavement in question is determined to be acceptable, the Engineer may allow the mix to remain in place at no pay for the mix, asphalt binder and other mix components. If the mix and/or pavement represented by the falsified results is determined not to be acceptable, remove and replace with mix, which complies with the Specifications. Payment will be made for the actual quantities of materials required to replace the falsified quantities, not to exceed the original amounts.

#### QUALITY ASSURANCE

Page 6-18, **Article 609-6**

In Item 1 under Plant Mix Quality Assurance, substitute "5 percent" for "10 percent".

In Item 2 under Plant Mix Quality Assurance, substitute "sampling and testing procedures" for "tests".

In Item 4 under Plant Mix Quality Assurance, add "for that increment" after the word "sample".

In Item 5 under Plant Mix Quality Assurance, add "at a frequency equal to or greater than 10 percent of the QC sample frequency"; or

Insert the following after Item 5 under Plant Mix Quality Assurance:

6. By any combination of the above.

Delete the paragraph below Plant Mix Quality Assurance, and replace with the following:

The Engineer will conduct assurance tests on both split QC samples taken by the Contractor and verification samples taken by the Department. These samples may be the regular quality control samples or a sample selected by the Engineer from any location in the process or verification samples taken at random by the Department. The frequency will be equal to or greater than 5 percent of that required of the Contractor as stated in Subarticle 609-5(C)2. The Engineer may select any or all samples for assurance testing.

In Item 1 under Density Quality Assurance, delete the wording at the end of the sentence "at a frequency equal to or greater than 10 percent of the frequency required of the Contractor".

In Item 3 under Density Quality Assurance, substitute 5 percent for 10 percent.

Page 6-19, Article 609-6

In Item 4 under Density Quality Assurance, add “at a frequency equal to or greater than 10 percent of the QC sample frequency.”

Insert the following after Item 4 under Density Quality Assurance:

- 5. By periodically directing the recalculation of random numbers for the Quality Control core or nuclear density test locations. The original QC test locations may be tested by QA and evaluated as verification tests.

LIMITS OF PRECISION

Page 6-19, Article 609-6

In the limits of precision table, delete the last three rows and substitute the following:

QA retest of prepared QC Gyratory Compacted

Volumetric Specimens	± 0.015
Retest of QC Core Sample	± 1.2% (% Compaction)
Comparison of QA Core Sample	± 2.0% (% Compaction)
QA Verification Core Sample	± 2.0% (% Compaction)
Nuclear Comparison of QC Test	± 2.0% (% Compaction)
QA Nuclear Verification Test	± 2.0% (% Compaction)

In the first sentence of the paragraph below the limits of precision table, insert “or verification test results” after “quality assurance test results”.

In the third sentence of the second paragraph below the limits of precision table, insert “or verification test results” after “quality assurance test results”.

ASPHALT CONCRETE PLANT MIX PAVEMENTS – DESCRIPTION

Page 6-20, Article 610-1

Insert the following after the last paragraph:

A high frequency of asphalt plant mix, density, or mix and density deficiencies occurring over an extended duration of time may result in future asphalt, which is represented by mix and/or density test results not in compliance with minimum specification requirements, being excluded from acceptance at an adjusted contract unit price in accordance with Article 105-3. This acceptance process may apply to all asphalt produced and /or placed and may continue until the Engineer determines a history of quality asphalt production and placement is reestablished.

## MATERIALS

Page 6-21, **Article 610-2**

Delete reference of Anti-strip additive (chemical) to **Article 1020-2** and substitute **Article 1020-8**.

## COMPOSITION OF MIXTURES (MIX DESIGN AND JOB MIX FORMULA)

Page 6-21, **Subarticle 610-3(A)**

At the end of the second paragraph, add the following sentence:

In addition, submit Superpave gyratory compactor printouts for all specimens compacted at  $N_{des}$  and  $N_{max}$  during the mix design process.

Insert the following paragraph after the second paragraph:

For the final surface layer of the specified mix type, use a mix design with an aggregate blend gradation above the maximum density line on the 2.36 mm and larger sieves.

Insert the following at the end of the third paragraph:

When the percent of binder contributed from RAS or a combination of RAS and RAP exceeds 20 percent of the total binder in the completed mix, the virgin binder PG grade shall be one grade below (both high and low temperature grade) the binder grade specified in Table 610-2 for the mix type.

Delete the fourth paragraph and substitute the following:

For Type S 12.5D mixes, the maximum percentage of reclaimed asphalt material is limited to 15% and shall be produced using virgin asphalt binder grade PG 76-22. For all other recycled mix types, when the percentage of RAP is 15 percent or less of the total mixture, the virgin binder PG grade shall be as specified in Table 610-2 for the specified mix type. When the percentage of RAP is greater than 15 but not more than 25 percent of the total mixture, the virgin binder PG grade shall be one grade below (both high and low temperature grade) the specified grade for the mix type. When the percentage of RAP is greater than 25 percent of the total mixture, the Engineer will establish and approve the asphalt binder grade.

Page 6-22, **Subarticle 610-3(A)**

Insert the following sentence at the end of the Item 4:

If natural sand is utilized in the proposed mix design, determine and report the Uncompacted Void Content of the natural sand in accordance with AASHTO T-304, Method A.

Page 6-23, **Subarticle 610-3(A)**

Under the quantities of mix components insert the following sentence:

When requested by the Engineer, submit to the Department’s Materials and Tests Unit, in Raleigh, six (6) Superpave Gyratory Compactor specimens compacted to a height of 75 mm and to a void content (VTM) of 4.0% +/- 0.5% for performance rut testing with the Asphalt Pavement Analyzer.

JOB MIX FORMULA

Page 6-24, **Subarticle 610-3(C)**

Delete Table 610-1 and associated notes. Substitute the following:

**TABLE 610-1  
SUPERPAVE AGGREGATE GRADATION DESIGN CRITERIA**

Standard d	Percent Passing Criteria (Control Points)											
	Mix Type (Nominal Maximum Aggregate Size)											
	4.75 mm (a)		9.5 mm (c)		12.5 mm (c)		19.0 mm		25.0 mm		37.5 mm	
(mm)	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.	Min.	Max.
50.0												100.0
37.5									100.0		90.0	100.0
25.0							100.0		90.0	100.0		90.0
19.0					100.0		90.0	100.0		90.0		
12.5				100.0	90.0	100.0		90.0				
9.5	100.0		90.0	100.0		90.0						
4.75	90.0	100.0		90.0								
2.36	65.0	90.0	32.0(b)	67.0(b)	28.0	58.0	23.0	49.0	19.0	45.0	15.0	41.0
1.18												
0.600												
0.300												
0.150												
0.075	4.0	8.0	4.0	8.0	4.0	8.0	3.0	8.0	3.0	7.0	3.0	6.0

- (a) For Type S 4.75A, a minimum of 50% of the aggregate components shall be manufactured material from the crushing of stone.
- (b) For Type SF 9.5A, the percent passing the 2.36mm sieve shall be a minimum of 60% and a maximum of 70%.
- (c) For the final surface layer of the specified mix type, use a mix design with an aggregate blend gradation above the maximum density line on the 2.36 mm and larger sieves.

Page 6-25, Subarticle 610-3(C),

Delete Table 610-2 and associated notes. Substitute the following:

**TABLE 610-2  
SUPERPAVE MIX DESIGN CRITERIA**

Mix	Design ESALs	Binder PG	Compaction Levels			Volumetric Properties (c)			
Type	millions	Grade	No. Gyration @			VMA	VTM	VFA	%Gmm
(f)	(a)	(b)	N <sub>ini</sub>	N <sub>des</sub>	N <sub>max</sub>	% Min.	%	Min. - Max.	@ N <sub>ini</sub>
S-4.75A	<0.3	64 -22	6	50	75	20.0	7.0-15.0		
SF-9.5A	<0.3	64 -22	6	50	75	16.0	3.0 - 5.0	70 - 80	≤ 91.5
S-9.5B	0.3 - 3	64 -22	7	75	115	15.0	3.0 - 5.0	65 - 80	≤ 90.5
S-9.5C	3 - 30	70 -22	8	100	160	15.0	3.0 - 5.0	65 - 76	≤ 90.0
S-12.5C	3 - 30	70 -22	8	100	160	14.0	3.0 - 5.0	65 - 75	≤ 90.0
S-12.5D	> 30	76 -22	9	125	205	14.0	3.0 - 5.0	65 - 75	≤ 90.0
I-19.0B	< 3	64 -22	7	75	115	13.0	3.0 - 5.0	65 - 78	≤ 90.5
I-19.0C	3 - 30	64 -22	8	100	160	13.0	3.0 - 5.0	65 - 75	≤ 90.0
I-19.0D	> 30	70 -22	9	125	205	13.0	3.0 - 5.0	65 - 75	≤ 90.0
B-25.0B	< 3	64 -22	7	75	115	12.0	3.0 - 5.0	65 - 78	≤ 90.5
B-25.0C	> 3	64 -22	8	100	160	12.0	3.0 - 5.0	65 - 75	≤ 90.0
B-37.5C	> 3	64 -22	8	100	160	11.0	3.0 - 5.0	63 - 75	≤ 90.0
	<i>Design Parameter</i>				<i>Design Criteria</i>				
All	1. %G <sub>mm</sub> @ N <sub>max</sub>				≤ 98.0% (d)				
Mix	2. Dust to Binder Ratio (P <sub>0.075</sub> / P <sub>be</sub> )				0.6 - 1.4				
Types	3. Retained Tensile Strength (TSR) (AASHTO T 283 Modified)				85 % Min. (e)				

- Notes:**
- (a) Based on 20 year design traffic.
  - (b) When Recycled Mixes are used, select the binder grade to be added in accordance with Subarticle 610-3(A).
  - (c) Volumetric Properties based on specimens compacted to N<sub>des</sub> as modified by the Department.
  - (d) Based on specimens compacted to N<sub>max</sub> at selected optimum asphalt content.
  - (e) AASHTO T 283 Modified (No Freeze-Thaw cycle required). TSR for Type S 4.75A, Type B 25.0 and Type B 37.5 mixes is 80% minimum.
  - (f) Mix Design Criteria for Type S 4.75A may be modified subject to the approval of the Engineer

WEATHER, TEMPERATURE, AND SEASONAL LIMITATIONS FOR PRODUCING AND PLACING ASPHALT MIXTURES

Page 6-26, **Article 610-4, Table 610-3**

Delete the title of **Table 610-3** and substitute the following title:

**ASPHALT PLACEMENT- MINIMUM TEMPERATURE REQUIREMENTS**

In the first column, third row; delete reference to the ACSC Types S 9.5A and S 12.5B mix.

Add the following minimum placing temperatures for mix types S 4.75A and SF 9.5A.

<b>Asphalt Concrete Mix Type</b>	<b>Minimum Air Temperature</b>	<b>Minimum Road Surface Temperature</b>
ACSC, Type S 4.75A, SF 9.5A	40°F (5°C)	50°F (10°C)

SPREADING AND FINISHING

Page 6-32, **Article 610-8**

Insert the following after the second sentence within the sixth paragraph.

Take necessary precautions during production, loading of trucks, transportation, truck exchanges with paver, folding of the paver hopper wings, and conveying material in front of the screed to prevent segregation of the asphalt mixtures.

Page 6-32, **Article 610-8**

Delete the last paragraph beginning on this page and continuing on the next page and substitute the following:

Use pavers equipped with an electronic screed control that will automatically control the longitudinal profile and cross slope of the pavement. Control the longitudinal profile through the use of either a mobile grade reference(s), including mechanical, sonic and laser grade sensing and averaging devices, an erected string line(s) when specified, joint matching shoe(s), slope control devices or the approved methods or combination of methods. Unless otherwise specified, use a mobile grade reference system capable of averaging the existing grade or pavement over a minimum 30 foot (9.1 meter) distance or by non-contacting laser or sonar type ski with at least four referencing stations mounted on the paver at a minimum length of 24 feet. Establish the position of the reference system such that the average profile grade is established at the approximate midpoint of the system. The transverse cross-slope shall be controlled as directed by the Engineer.

Page 6-33, **Article 610-8**

Delete the second full paragraph on this page and substitute the following:

Use the 30 foot (9.1 meter) minimum length mobile grade reference system or the non-contacting laser or sonar type ski with at least four referencing stations mounted on the paver at a minimum length of 24 feet to control the longitudinal profile when placing the initial lanes and all adjacent lanes of all courses, including resurfacing and asphalt in-lays, unless other specified or approved. A joint matching device short (6 inch [152.4 mm] shoes) may be used only when approved.

At the end of the third full paragraph, add the following sentence:

Waiver of the use of automatic screed controls does not relieve the Contractor of achieving plan grades and cross-slopes.

Insert the following as the last paragraph:

Repair any damage caused by hauling equipment across structures at no additional cost to the Department.

**DENSITY REQUIREMENTS**

Page 6-34, **Article 610-10,**

Delete **Table 610-4** and substitute the following table and associated notes:

**Table 610-4  
MINIMUM DENSITY REQUIREMENTS**

MIX TYPE	MINIMUM % of $G_{mm}$
SUPERPAVE MIXES	(Maximum Specific Gravity)
S 4.75A	85.0 <sup>(a,b)</sup>
SF 9.5A	90.0
S 9.5X, S 12.5X, I 19.0X, B 25.0X, B 37.5X	92.0

- (a) All S 4.75A pavement will be accepted for density in accordance with Article 105-3
- (b) Compaction to the above specified density will be required when the S 4.75 A mix is applied at a rate of 100 lbs/sy (55 kg/m<sup>2</sup>)



**Page 6-34, Article 610-10**

Delete the second paragraph and substitute the following:

Compact base and intermediate mix types (surface mixes not included) utilized for pavement widening of less than 4.0 feet (1.2 meters) and all mix types used in tapers, irregular areas and intersections (excluding full width travel lanes of uniform thickness), using equipment and procedures appropriate for the pavement area width and/or shape. Compaction with equipment other than conventional steel drum rollers may be necessary to achieve adequate compaction. Occasional density sampling and testing to evaluate the compaction process may be required. Densities lower than that specified in Table 610-4 will be accepted, in accordance with Article 105-3, for the specific mix types and areas listed directly above.

**SURFACE REQUIREMENTS AND ACCEPTANCE****Page 6-35, Article 610-12**

Delete the first paragraph and substitute the following:

Construct pavements using quality paving practices as detailed herein. Construct the pavement surface smooth and true to the plan grade and cross slope. Immediately correct any defective areas with satisfactory material compacted to conform with the surrounding area. Pavement imperfections resulting from unsatisfactory workmanship such as segregation, improper longitudinal joint placement or alignment, non-uniform edge alignment and excessive pavement repairs will be considered unsatisfactory and if allowed to remain in place will be accepted in accordance with Article 105-3.

When directed due to unsatisfactory laydown or workmanship, operate under the limited production procedures. Limited production for unsatisfactory laydown is defined as being restricted to the production, placement, compaction, and final surface testing (if applicable) of a sufficient quantity of mix necessary to construct only 2500 feet (750 meter) of pavement at the laydown width.

Remain on limited production until such time as satisfactory laydown results are obtained or until three consecutive 2500 foot (750 meter) sections have been attempted without achieving satisfactory laydown results. If the Contractor fails to achieve satisfactory laydown results after three consecutive 2500 foot (750 meter) sections have been attempted, cease production of that mix type until such time as the cause of the unsatisfactory laydown results can be determined. As an exception, the Engineer may grant approval to produce a different mix design of the same mix type if the cause is related to mix problem(s) rather than laydown procedures.

Mix placed under the limited production procedures for unsatisfactory laydown or workmanship will be evaluated for acceptance in accordance with Article 105-3.

## DENSITY ACCEPTANCE

Page 6-36, **Article 610-13**

Delete the second paragraph and substitute the following:

The pavement will be accepted for density on a lot by lot basis. A lot will consist of one day's production of a given job mix formula on a contract. As an exception, separate lots will be established when the one of the following occurs:

- (1) Portions of pavement are placed in both "New" and "Other" construction categories as defined below. A lot will be established for the portion of the pavement in the "New" construction category and a separate lot for the portion of pavement in the "Other" construction category.
- (2) Pavement is placed on multiple resurfacing maps, unless otherwise approved prior to paving. A lot will be established for each individual resurfacing map or portion thereof.
- (3) Pavement is placed simultaneously by multiple paving crews. A lot will be established for the pavement placed by each paving crew.
- (4) Pavement is placed in different layers. A lot will be established for each layer.
- (5) Control strips are placed during limited production.

The Engineer will determine the final category and quantity of each lot for acceptance purposes.

Page 6-36, **Article 610-13**

Delete the first sentence in the third paragraph and insert the following:

The "New" construction category will be defined as pavements of uniform thickness, exclusive of irregular areas, meeting all three of the following criteria:

Delete the sixth paragraph and substitute the following:

A failing lot for density acceptance purposes is defined as a lot for which the average of all test sections, and portions thereof, fails to meet the minimum specification requirement. If additional density sampling and testing, beyond the minimum requirement, is performed and additional test sections are thereby created, then all test results shall be included in the lot average. In addition, any lot or portion of a lot that is obviously unacceptable will be rejected for use in the work.

Page 6-36, **Article 610-13**

Delete the last paragraph and substitute the following:

Any density lot not meeting minimum density requirements detailed in Table 610-4 will be evaluated for acceptance by the Engineer. If the lot is determined to be reasonably acceptable, the mix will be paid at an adjusted contract price in accordance with Article 105-3. If the lot is determined not to be acceptable, the mix will be removed and replaced with mix meeting and compacted to the requirement of these specifications.

**BASIS OF PAYMENT, ASPHALT PAVEMENTS**

Page 6-37, **Article 610-16**

Add the following to the second paragraph:

The quantity of hot mix asphalt pavement, measured as provided in Article 610-15, will be paid for at the contract unit prices per ton (metric ton) for “Asphalt Concrete Surface Course, Type S 4.75A, and SF 9.5A”.

Add the following to the payment item description:

Asphalt Concrete Surface Course, Type S 4.75A.....	Ton (Metric Ton)
Asphalt Concrete Surface Course, Type SF 9.5A.....	Ton (Metric Ton)

Delete reference to the Asphalt Concrete Surface Course, Types S 9.5A and S 12.5B in both the second paragraph and in the payment description.

**ASPHALT BINDER FOR PLANT MIX - METHOD OF MEASUREMENT**

Page 6-39, **Article 620-4**

Delete the first sentence of the second paragraph and substitute the following:

Where recycled plant mix is being produced, the grade of asphalt binder to be paid for will be the grade for the specified mix type as required in Table 610-2 unless otherwise approved.

**OPEN-GRADED ASPHALT FRICTION COURSE CONSTRUCTION REQUIREMENTS**

Page 6-43, **Article 650-5**

Add the following paragraph after the first paragraph:

Do not place open-graded asphalt friction course between October 31 and April 1 of the next year, unless otherwise approved. Place friction course, Type FC-1 mixes, only when the road surface temperature is 50°F (10°C) or higher and the air temperature is 50°F (10°C) or higher.

The minimum air temperature for Type FC-1 Modified and FC-2 Modified mixes will be 60°F (15°C).

**AGGREGATES FOR ASPHALT PLANT MIXES**

Page 10-34, **Subarticle 1012-1(B)4**

Delete and substitute the following:

(4) Flat and Elongated Pieces:

Use coarse aggregate meeting the requirements of Table 1012-1 for flat and elongated pieces when tested in accordance with ASTM D 4791 (Section 8.4) on the No. 4 (4.75 mm) sieve and larger with a 5:1 aspect ratio (maximum to minimum) for all pavement types, except there is no requirement for Types S 4.75A, SF 9.5A, and S 9.5B.

Page 10-35, **Table 1012-1**

Delete **Table 1012-1** and substitute the following:

**Table 1012-1  
AGGREGATE CONSENSUS PROPERTIES<sup>(a)</sup>**

Mix Type	Course Aggregate Angularity <sup>(b)</sup>	Fine Aggregate Angularity % Minimum	Sand Equivalent % Minimum	Flat & Elongated 5 : 1 Ratio % Maximum
	ASTM D 5821	AASHTO T 304 Method A	AASHTO T 176	ASTM D 4791 Section 8.4
S 4.75 A		40	40	
SF 9.5 A S 9.5 B I 19.0 B B 25.0 B	75 / -	40	40	10 <sup>(c)</sup>
S 9.5 C S 12.5 C I 19.0 C B 25.0 C B 37.5 C	95 / 90	45	45	10
S 12.5 D I 19.0 D	100 / 100	45	50	10
OGAFC	100 / 100	N/A	N/A	10

(a) Requirements apply to the course aggregate blend and/or fine aggregate blend

(b) 95/90 denotes that 95% of the course aggregate (+No.4 or + 4.75mm sieve) has one fractured face and 90% has two or more fractured faces.

(c) Does not apply to Mix Types SF 9.5 A or S 9.5 B

Page 10-36, **Subarticle 1012-1(C)1**

Insert the following after the fourth paragraph:

When natural sand is utilized in “C” or “D” level asphalt mixes, do not exceed the maximum natural sand percentage in the mix design and/or production aggregate blend detailed in Table 1012-1A.

**Table 1012-1A**

Uncompacted Void Content of Fine Aggregate AASHTO T 304 Method A	Maximum Percent Natural Sand Included in Mix Design and/or Production*
Less than 42.0	10
Equal to 42.0 to 44.9	15
Equal to 45.0 and greater	20

\*Maximum percent natural sand may be exceeded with approval from Pavement Construction Engineer upon satisfactory evaluation of pavement performance testing

**FINE AGGREGATE ANGULARITY**

Page 10-36, **Subarticle 1012-1(C)6**

Delete reference to AASHTO TP 33 Method A and substitute AASHTO T 304, Method A.

Page 10-37, **Subarticle 1012-1(H)**

Delete this Subarticle. It is a duplicate of Subarticle 1012-1(F) located on Page 10-36.

**ASPHALT BINDER**

Page 10-46, **Article 1020-2**

Delete the first paragraph and substitute the following:

Use Performance Graded Asphalt Binder meeting the requirements of AASHTO M 320. See Article 610-3 for the specified grades. Submit a Quality Control Plan for asphalt binder production in conformance with the requirements of AASHTO R 26 to the Materials and Tests Unit.

SP6R01

**ASPHALT BINDER CONTENT OF ASPHALT PLANT MIXES:**

11-21-00<sub>R</sub>

The approximate asphalt binder content of the asphalt concrete plant mixtures used on this project will be as follows:

Asphalt Concrete Base Course, Type B 25.0__	4.3%
Asphalt Concrete Intermediate Course, Type I 19.0__	4.7%
Asphalt Concrete Surface Course, Type S 4.75A	7.0%
Asphalt Concrete Surface Course, Type SF 9.5A	6.5%
Asphalt Concrete Surface Course, Type S 9.5__	6.0%
Asphalt Concrete Surface Course, Type S 12.5__	5.5%

The actual asphalt binder content will be established during construction by the Engineer within the limits established in the Standard Specifications or Project Special Provisions.

SP6R15

**ASPHALT PLANT MIXTURES:**

7-1-95<sub>c</sub>

Place asphalt concrete base course material in trench sections with asphalt pavement spreaders made for the purpose or with other equipment approved by the Engineer.

SP6R20

**PRICE ADJUSTMENT - ASPHALT BINDER FOR PLANT MIX:**

11-21-00

Price adjustments for asphalt binder for plant mix will be made in accordance with Section 620 of the Standard Specifications as modified herein.

The base price index for asphalt binder for plant mix is \$210.39 per ton (metric ton).

This base price index represents an average of F.O.B. selling prices of asphalt binder at supplier's terminals on December 1, 2004.

SP6R25

**CONSTRUCTION SURVEYING:**

01-20-04

Add the following after the first sentence of Section 801-1 of the January 2002 Standard Specifications:

Provide a stakeout of areas where an environmental permit is required prior to performing any construction in or adjacent to these areas. Stake out limits of the permitted work areas according to the approved permit drawings. Provide clear delineation by use of pink or other highly visible flagging. Insure construction limits do not exceed approved permitted work areas. Immediately notify the Resident Engineer of any variations of the stakeout limits when compared to the approved permit drawings.

Replace the fifth paragraph of Section 801-4 of the January 2002 Standard Specifications with the following:

Partial payments for the item of "Construction Surveying" will be made on each particular payment estimate based upon the percentage complete of the item of "Construction Surveying" as determined by the Engineer. The Contractor is required to submit a certified statement each month indicating the percentage of "Construction Surveying" work completed. The Resident Engineer will determine if the amount indicated is reasonably correct and the Resident Engineer will pay accordingly on the next partial pay estimate.

SP8R02

**DISPOSAL OF WASTE AND DEBRIS:**

2-19-02

Revise the 2002 Standard Specifications as follows:

**Page 8-9, Subarticle 802-2(7. Buffer Zones:)**

At the end of the last sentence in this subarticle, add the words "unless superseded by an environmental permit."

SP8R03

**GUARDRAIL POSTS AND OFFSET BLOCKS:**

06-22-04

Revise the *2002 Standard Specifications* as follows:

Page 10-69, Subarticle 1046-3

Delete this sub-article in its entirety and replace with the following:

**1046-3 POSTS AND OFFSET BLOCKS.**

**(A) General:**

The Contractor may at his option furnish either of the following types of steel guardrail posts. Only one type of post will be permitted at any one continuous installation. Use structural steel posts throughout the project, unless otherwise directed or detailed in the plans.

1. Steel W6 x 8.5 or W6 x 9.0 posts
2. Steel 4.5" x 6.0" "C" shape posts (C150 x 12.2 kg/m)

The Contractor may at his option furnish either of the following types of treated timber posts if specifically directed or detailed in the plans. Only one type of post will be permitted at any one continuous installation.

1. Timber 6" x 8" (152 mm x 203 mm) posts.
2. Timber 8" x 8" (203 mm x 203 mm) posts.

**(B) Structural Steel Posts:**

Fabricate steel posts for guardrail of the size and weight shown on the plans from structural steel complying with the requirements of Section 1072. Metal from which C shape posts are fabricated shall meet the requirements of ASTM A570 for any grade of steel, except that mechanical requirements shall meet the requirements of ASTM A36. Punch or drill the holes for connecting bolts. Burning will not be permitted. After fabrication, the posts shall be galvanized in accordance with Section 1076.

**(C) Treated Timber Posts:**

Timber guardrail posts shall be of treated southern pine meeting the requirements of Article 1082-2 and 1082-3.

Bore bolt holes to a driving fit for the bolts. A minus tolerance of 1 percent will be allowed in the length of the post. Perform all framing and boring before the posts receive preservative treatment.

**(D) Offset Blocks:**

Provide 8-inch deep recycled plastic or composite offset blocks that have been approved for use with the guardrail shown in the standard drawings and/or plans. Only one type of offset block will be permitted at any one continuous installation. Prior to beginning the installation of recycled offset block, submit the FHWA acceptance letter for each type of block to the Engineer for approval.

Treated timber offset blocks with steel beam guardrail will not be allowed unless required by Specifications, directed by the Engineer or detailed in the plans. Steel offset blocks with steel beam guardrail will not be allowed.

Recycled plastic or composite offset blocks shall be made from no less than 50% recycled plastic or composite, and shall meet the following minimum requirements:

- Specific Gravity: .....0.950
- Compressive Strength in Lateral Direction: .....1600 psi (11 MPa)
- Maximum Water Absorption: .....10% by weight
- Maximum Termite and Ant Infestation: .....10%
- Testing.....Shall pass NCHRP Report 350,  
Test Level 3 by CRASH TESTING

Revise the *2002 Standard Roadway Drawings* as follows:

Sheet 4 of 6, Standard 862.03, delete the note and substitute the following:

Note: The midpost and offset block of the WTR section will require special bolt hole drilling in the thrie beam offset block and line post.

SP8R57



**GUARDRAIL ANCHOR UNITS, (SPECIAL):**

**12-15-98**

**DESCRIPTION**

The Contractor shall furnish and install guardrail anchor units with the applicable requirements of Section 862 of the Standard Specifications and at locations shown in the plans.

**MATERIALS**

Guardrail anchor unit (SKT) (TL-2) as manufactured by:

ROAD SYSTEMS, INC.  
3616 OLD HOWARD COUNTY AIRPORT  
BIG SPRING, TEXAS 79720  
TELEPHONE: (915) 263-2435

**CONSTRUCTION**

Installation shall be performed in accordance with the details in the plans and details and assembling instructions furnished by the Manufacturer.

Guardrail end delineation is required on all approach and trailing end guardrail buffer end sections for both temporary and permanent. Guardrail end delineation consists of yellow reflective sheeting applied to the entire buffer end section of the guardrail in accordance with Section 1088-3 of the Standard Specifications and is incidental to the cost of the guardrail anchor unit.

**MEASUREMENT AND PAYMENT**

Measurement and payment will be made in accordance with Articles 862-5 and 862-6 of the Standard Specifications.

Payment will be made under:

Guardrail Anchor Units, (SKT TL-2) .....Each

SP8R65

**GUARDRAIL ANCHOR UNITS, TYPE 350:**

**04-20-04**

**DESCRIPTION**

Furnish and install guardrail anchor units in accordance with the details in the plans, the applicable requirements of Section 862 of the Standard Specifications, and at locations shown in the plans.

**MATERIALS**

The Contractor may at his option, furnish any one of the guardrail anchor units.

Guardrail anchor unit (ET-2000) as manufactured by:

TRINITY INDUSTRIES, INC.  
2525 N. STEMMONS FREEWAY  
DALLAS, TEXAS 75207  
TELEPHONE: 1-800-644-7976

The guardrail anchor unit (SKT 350) as manufactured by:

ROAD SYSTEMS, INC.  
3616 OLD HOWARD COUNTY AIRPORT  
BIG SPRING, TEXAS 79720  
TELEPHONE: (915) 263-2435

Prior to installation the Contractor shall submit to the Engineer:

1. FHWA acceptance letter for each guardrail anchor unit certifying it meets the requirements of NCHRP Report 350, Test Level 3, in accordance with Section 106-2 of the Standard Specifications.
2. Certified working drawings and assembling instructions from the manufacturer for each guardrail anchor unit in accordance with Section 105-2 of the Specifications.

No modifications shall be made to the guardrail anchor unit without the express written permission from the manufacturer. Perform installation in accordance with the details in the plans, and details and assembling instructions furnished by the manufacturer.

**CONSTRUCTION**

Guardrail end delineation is required on all approach and trailing end sections for both temporary and permanent installations. Guardrail end delineation consists of yellow reflective sheeting applied to the entire end section of the guardrail in accordance with Section 1088-3 of the Standard Specifications and is incidental to the cost of the guardrail anchor unit.

**MEASUREMENT AND PAYMENT**

Measurement and payment will be made in accordance with Articles 862.5 and 862-6 of the Standard Specifications.

Payment will be made under:

Guardrail Anchor Units, Type 350 .....Each

SP8R65

**AGGREGATE PRODUCTION:****11-20-01**

Provide aggregate from a producer who utilizes the new Aggregate Quality Control/Quality Assurance Program that is in effect at the time of shipment.

No price adjustment is allowed to contractors or producers who utilize the new program. Participation in the new program does not relieve the producer of the responsibility of complying with all requirements of the Standard Specifications. Copies of this procedure are available upon request from the Materials and Test Unit.

SP10R05

**CONCRETE BRICK AND BLOCK PRODUCTION:****11-20-01**

Provide concrete brick and block from a producer who utilizes the new Solid Concrete Masonry Brick/Unit Quality Control/Quality Assurance Program that is in effect on the date that material is received on the project.

No price adjustment is allowed to contractors or producers who utilize the new program. Participation in the new program does not relieve the producer of the responsibility of complying with all requirements of the Standard Specifications. Copies of this procedure are available upon request from the Materials and Test Unit.

SP10R10

**FINE AGGREGATE:****11-19-02**

Revise the 2002 Standard Specifications as follows:

Page 10-17, Table 1005-2

Make the following change to the table:

For Standard Size 2MS the following gradation change applies.

The minimum percent shown for material passing the No. 8 (2.36mm) sieve has been changed from 84 to **80**.

SP10R15

**BORROW MATERIAL****02-17-04**

Revise the 2002 Standard Specifications as follows:

Page 10-44

Section 1018-2 II (b) Delete the last sentence in its entirety.

SP10R17

**TRAFFIC CONTROL**

**01-18-05**

Revise the *2002 Standard Specifications* as follows:

Article 1089-1 WORK ZONE SIGNS is deleted. Substitute the following:

(A) General:

Rigid sign retroreflective sheeting requirements for Types VII, VIII and IX (prismatic) fluorescent are described in Tables 1089-A, 1089-B and 1089-C. Cover the entire sign face of the sign substrate with NCDOT approved Type VII, VIII or IX (prismatic) fluorescent orange reflective sheeting. Apply the reflective sheeting in a workmanlike manner so that there are no bubbles or wrinkles in the material.

Roll-up sign retroreflective requirements are described in Table 1089-D.

1. Work Zones Signs (Stationary)

Use Type VII, VIII or IX (prismatic) fluorescent orange retroreflective sheeting that meets the following reflective requirements in Tables 1089-A, 1089-B or 1089-C respectively. Use approved composite or aluminum for sign backing. Signs and sign supports must meet or exceed NCHRP 350 requirements for Breakaway Devices.

<b>Table 1089-A</b>		
Minimum Coefficient of Retroreflection $R_A$ for TYPE VII Fluorescent Orange Sheeting (Candelas per lux per square meter)		
Observation Angle	Entrance Angle	
	-4°	30°
0.1°	300	170
0.2°	230	130
0.5°	72	41

**Table 1089-B**  
Minimum Coefficient of Retroreflection  $R_A$  for  
TYPE VIII Fluorescent Orange Sheeting  
(Candelas per lux per square meter)

Observation Angle	Entrance Angle	
	-4°	30°
0.1°	300	135
0.2°	210	95
0.5°	75	35

**Table 1089-C**  
Minimum Coefficient of Retroreflection  $R_A$  for  
TYPE IX Fluorescent Orange Sheeting  
(Candelas per lux per square meter)

Observation Angle	Entrance Angle	
	-4°	30°
0.1°	200	110
0.2°	115	65
0.5°	72	41
1.0°	24	14

2. Work Zones Signs (Barricade Mounted)

Use approved composite or roll-up signs for barricade mounted sign substrates. Approved composite barricade mounted warning signs (black on orange) must be Type VII, VIII or IX sheeting which meet the retroreflective requirements of Table 1089-A, 1089-B or 1089-C. Roll-up mounted barricade warning signs (black on orange) must meet the retroreflective requirements in Table 1089-D. Sign and barricade assembly must meet or exceed the requirements of NCHRP 350 for Work Zone Category II Devices.

3. Work Zones Signs (Portable)

Use approved composite or roll-up sign substrates on portable sign stands.

Composite - Use Type VII, VIII or IX (prismatic) fluorescent orange retroreflective sheeting that meets the following reflective requirements in Tables 1089-A, 1089-B or 1089-C. Signs and sign supports must meet or exceed NCHRP 350 requirements for Breakaway Devices.

Roll-up Signs - Use fluorescent orange retroreflective roll-up signs that meet the following reflective requirements:

<b>Table 1089-D</b>		
Minimum Coefficient of Retroreflection $R_A$ for Fluorescent Orange Roll-Up Signs (Candelas per lux per square meter)		
Observation Angle	Entrance Angle	
	-4°	30°
0.1°	300	120
0.2°	200	80
0.5°	90	34

Use roll up signs that have a minimum 3/16” x 1 1/4” horizontal rib and 38” x 1 1/4” vertical rib and has been crash test to meet NCHRP 350 requirements and Traffic Control qualified by the Work Zone Traffic Control Unit.

Add the following after 1089-1(C):

(D) Warranty

Warranty requirements for rigid sign retroreflective sheeting Types VII, VIII and IX are described in Section 1093-9 (F) and Tables 1089 A, B and C. Roll-up fluorescent orange retroreflective signs will maintain 80% of its retroreflectivity (Table 1089-D) for years 1 – 2 and 50% for year 3.

Rigid and Rollup Fluorescent orange signs will maintain a Fluorescence Luminance Factor ( $Y_F$ )\* of 13% for three (3) years.

\*Fluorescence Testing Method is described in ASTM E2301 Test Methods for Fluorescent Retro reflective Sheeting.

Rigid and Roll up fluorescent orange signs shall maintain a total Luminance Factor (Y) of 25 for three (3) years and conform to the requirements of Table 1089-E when measured in accordance with ASTM D4956.

<b>Table 1089-E</b>									
Fluorescent Orange colorimetric requirements									
Color	1		2		3		4		y
	x	y	x	y	x	y	x	y	
Fluorescent Orange	0.583	0.416	0.535	0.400	0.595	0.351	0.645	0.355	

BARRICADES

**Article 1089-3(A) General**, delete both paragraphs and substitute the following:

Type III Barricades shall be constructed of perforated square steel tubing and/or angle iron. Provide Type III barricades that use a cross member or stabilization bar and meet the requirements of NCHRP 350 for Work Zone Category II Devices with composite and roll-up signs attached.

Use approved composite or plastic barricade rails that have a smooth face and have alternating orange and white retroreflective stripes that slope at an angle of 45 degrees.

**Article 1089-3(C) Reflective Sheeting**, delete the first paragraph only and substitute the following:

Use Type VII, VIII or IX (prismatic) retroreflective fluorescent orange sheeting on both sides of the barricade rails. The rail sheeting retroreflectivity values shall meet the retroreflectivity requirements in Table 1089-A, 1089-B or 1089-C and shall be listed on the Department’s approved product list or accepted as traffic qualified by the Traffic Control Unit.

SP10R30

**DRUMS:**

**07-16-02**

Revise the 2002 Standard Specifications as follows:

Page 10-195, Subarticle 1089-5(C)

Delete the first (1<sup>st</sup>) sentence of the first (1<sup>st</sup>) paragraph and insert the following:

“Provide a minimum of three orange and two white alternating horizontal circumferential stripes covering the entire outside with each drum.”

SP11R05

**WORK ZONE SIGNS**

**01-18-05**

Revise the *Standard Specifications* as follows:

DESCRIPTION

Page 11-5, **Article 1110-1 Description**

Replace the second paragraph with the following:

Furnish, install, maintain and relocate portable work zone signs and portable work zone sign stands in accordance with the plans and specifications. When portable work zone signs and portable work zone sign stands are not in use for periods longer than 30 minutes, collapse sign stand and reinstall once work begins.

Replace the last sentence in the third paragraph with the following:

Use work zone signs (portable) only with portable work zone sign stands specifically designed for one another. Work Zone Signs (portable) may be roll up or approved composite.

MATERIALS

Page 11-5, **Article 1110-2 Part (A) General:**

Add the following:

Barricade Mounted Signs.....Article 1089-3

MATERIAL QUALIFICATIONS

Page 11-5, **Article 1110-2 Part (B) Material Qualifications.**

Delete the first sentence in the first paragraph and replace with the following:

Provide portable work zone sign stands, portable signs and sign sheeting which are listed on the North Carolina Department of Transportation’s approved product list or accepted as traffic qualified by the Traffic Control Unit.

Delete “Traffic Control Section” in the second sentence of the first paragraph and insert “Traffic Control Unit”.

CONSTRUCTION METHODS

Page 11-6, Article 1110-3 CONSTRUCTION METHODS.

Replace **Article 1110-3 (B) Work Zone Signs (Barricade Mounted)** with the following:

Mount approved composite or roll-up signs to barricade rails so that the signs do not cover more than 50 percent of the top two rails or 33 percent of the total area of the three rails. Signs are to be mounted a minimum of 1’ from the ground to the bottom of the sign.

Replace **Article 1110-3 (C, 2) Work Zone Signs (Portable)** with the following:

Install portable work zone signs to carry roll-up or approved composite at a minimum height of 1’ from the bottom of the sign to the ground on two lane-two way roadways.

Install portable work zone signs to carry roll-up or approved composite at a minimum height of 5’ from the bottom of the sign to the ground on multi-lane roadways.



METHOD OF MEASUREMENT AND BASIS OF PAYMENT

Method of Measurement and Basis of Payment will be in accordance with Section 1110-5 and 1110-6 of the *Standard Specifications*.

SP11R15

**BARRICADES**

**01-18-05**

Revise the 2002 *Standard Specifications* as follows:

Page 11- 12, **Article 1145-2 Materials**, delete the contents and substitute the following:

(A) General

Refer to Division 10:

Barricades..... Article 1089-3

(B) Material Qualifications

Provide Type III barricades and barricade rails that are listed on the North Carolina Department of Transportation’s approved product list or accepted as traffic qualified by the Traffic Control Unit. For more information on the Traffic Qualification process, contact the Traffic Control Unit at Century Center Building B, 1020 Birch Ridge Drive, Raleigh, NC 27610; (919) 250-4159, or see the approved product list on the NCDOT web site at: [www.doh.dot.state.nc.us/construction/tc/Apv\\_Prod/apv\\_prod.htm](http://www.doh.dot.state.nc.us/construction/tc/Apv_Prod/apv_prod.htm)

(C) Historical Performance:

Historical performance of Type III barricades and barricade rails will be used in determining future use of the material by the NCDOT, even if the Type III Barricade is traffic-qualified. Poor past or poor current performance of Type III Barricades at any site, whether or not related to a specific contract may be grounds for non-acceptance of a product on any project under contract.

MEASUREMENT AND PAYMENT

Method of Measurement and Basis of Payment will be in accordance with Section 1145-5 and 1145-6 of the *Standard Specifications*.

SP11R20

**PAVEMENT MARKING GENERAL REQUIREMENTS:**

**7/16/02**

Revise the 2002 Standard Specifications as follows:

Page 12-10, Subarticle 1205-3(J)

Delete the first (1<sup>st</sup>) sentence of the first (1<sup>st</sup>) paragraph and insert the following:

“Have at least one member of every pavement marking crew working on a project certified through the NCDOT Pavement Marking Technician Certification Process. For more information contact the Traffic Control, Marking and Delineation Section of the North Carolina Department of Transportation at 919-250-4151 or

<http://www.doh.dot.state.nc.us/preconstruct/traffic/congestion/TC/>”

SP12R01