

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	8 TON		
0007	0343000000-E	310	15" SIDE DRAIN PIPE	48 LF		
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	20 LF		
0009	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0010	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	270 TON		
0011	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	390 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	37 TON		
0013	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0014	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0015	2556000000-E	846	SHOULDER BERM GUTTER	12 LF		
0016	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0017	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0018	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (SKT TL-2)	3 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77, SHOP CURVED)	1 EA		
0020	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0021	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	3 EA		
0022	3649000000-E	876	PLAIN RIP RAP, CLASS B	2 TON		
0023	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	202 SY		
0024	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	39 SF		
0025	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	82 LF		
0026	4102000000-N	904	SIGN ERECTION, TYPE E	6 EA		
0027	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8 EA		
0028	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	399 SF		
0029	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	144 SF		
0030	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0031	4430000000-N	1130	DRUMS	30 EA		
0032	4435000000-N	1135	CONES	30 EA		
0033	4446100000-E	SP	BARRICADES (TYPE III)	88 LF		
0034	4455000000-N	1150	FLAGGER	33 MD		
0035	4460000000-N	1155	WARNING LIGHTS (TYPE B)	3 EA		
0036	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,788 LF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6000000000-E	1605	TEMPORARY SILT FENCE	160 LF		
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	250 TON		
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	320 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0044	6029000000-E	SP	SAFETY FENCE	550 LF		
0045	6030000000-E	1630	SILT EXCAVATION	350 CY		
0046	6036000000-E	1631	MATTING FOR EROSION CONTROL	520 SY		
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	770 LF		
0048	6070000000-N	SP	SPECIAL STILLING BASINS	1 EA		
0049	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0050	6087000000-E	1660	MOWING	1 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0055	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		
0056	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0058	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0059	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+42.00 -L-)	Lump Sum	L.S.	
0060	8096000000-E	SP	PILE EXCAVATION IN SOIL	110 LF		
0061	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	50 LF		
0062	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+42.00 -L-)	Lump Sum	L.S.	
0063	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	1,953.6 SF		
0064	8161000000-E	420	GROOVING BRIDGE FLOORS	2,278.1 SF		
0065	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	61.6 CY		
0066	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+42.00 -L-)	Lump Sum	L.S.	
0067	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,002 LB		
0068	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	31,900 LS		
0069	8364000000-E	450	HP12X53 STEEL PILES	480 LF		
0070	8391000000-N	450	STEEL PILE POINTS	16 EA		
0071	8503000000-E	460	CONCRETE BARRIER RAIL	106.56 LF		
0072	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	220 TON		
0073	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	240 SY		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0075	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1521/Jan07/Q61634.21/D371917900000/E75			Total Amount Of Bid For Entire Project :			

C200862
Haywood County

2/16/99

Contract No: C200862
County: Haywood

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General