

PROJECT NO.	SHEET NO.	TOTAL NO.
14CR.10451.1, 14CR.20451.4	5	9

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	SHOULDER RECONSTRUCTION SMI	3" MILLING SY	1 1/2" TO 2 1/2" MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	SF9.5A LEVELING TON	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	CONCRETE JOINT REPAIR SY
14CR.10451.1	Henderson	1	US74A	FROM BUNCOMBE CO. TO RUTHERFORD CO.	5	6.64	23	13.28	21,706		3,935	7,978	5,318	1,009	75	46
TOTAL FOR PROJ NO. 14CR.10451.1						6.64		13.28	21,706		3,935	7,978	5,318	1,009	75	46
14CR.20451.4	Henderson	2	SR1260	FROM SR1128 TO SR1259	1	0.87	20					909		55		
		3	SR1827	FROM SR1860 TO PVMT CHNG 1.87 MILE NORTH	4	1.87	18			175	62	1,465	733	139		
		4	SR1545	FROM US25 TO BUMCOMBE COUNTY LINE	2	1.35	20			200		1,410		85		
		5	SR1847	FROM SR1846 TO SR1846	3	1.34	21					1,050	525	98		
		6	SR1846	FROM SC LINE TO POLK CO. LINE	1	3.03	18					2,849		171		
TOTAL FOR PROJ NO. 14CR.20451.4						8.46				375	62	7,683	1,258	548		
GRAND TOTAL						15.1		13.28	21,706	375	3,997	15,661	6,576	1,557	75	46