

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201164

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+33.50)
0036000000-E	225	250	CY	UNDERCUT EXCAVATION
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0134000000-E	240	26	CY	DRAINAGE DITCH EXCAVATION
0318000000-E	300	20	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0366000000-E	310	76	LF	15" RC PIPE CULVERTS, CLASS III
0708000000-E	310	92	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	6	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1121000000-E	520	75	TON	AGGREGATE BASE COURSE
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1489000000-E	610	520	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	255	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	39	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2209000000-E	838	2	CY	ENDWALLS
2286000000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES
2355000000-N	840	2	EA	FRAME WITH GRATE, STD 840.29
2364000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.16
2556000000-E	846	180	LF	SHOULDER BERM GUTTER
2577000000-E	846	150	LF	CONCRETE EXPRESSWAY GUTTER
3150000000-N	862	10	EA	ADDITIONAL GUARDRAIL POSTS
3165000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE 350, WEATHERING STEEL)

ItemNumber	Sec #	Quantity	Unit	Description
3165000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, WEATHERING STEEL)
3360000000-E	863	380	LF	REMOVE EXISTING GUARDRAIL
3420000000-E	SP	450	LF	GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL (WEATHERED STEEL WITH WOOD POSTS)
3635000000-E	876	22	TON	PLAIN RIP RAP, CLASS II
3649000000-E	876	39	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	467	SY	FILTER FABRIC FOR DRAINAGE
4412100000-E	SP	574	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	154	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4445000000-E	1145	122	LF	BARRICADES (TYPE III)
4810000000-E	1205	7,200	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	24	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	210	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	265	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	165	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	2.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	70	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	1,235	LF	SAFETY FENCE
6030000000-E	1630	380	CY	SILT EXCAVATION
6036000000-E	1631	1,060	SY	MATTING FOR EROSION CONTROL

ItemNumber	Sec #	Quantity	Unit	Description
6038000000-E	SP	445	SY	PERMANENT SOIL REINFORCEMENT MAT
6042000000-E	1632	40	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	4	EA	SPECIAL STILLING BASINS
6084000000-E	1660	2.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.75	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

15-OCT-2004 06:59
B:\B3350\B3350.sum
JBGauthier AT RD203021