

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+33.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	26 CY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	76 LF		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	92 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
0012	1121000000-E	520	AGGREGATE BASE COURSE	75 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	520 TON		
0015	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	255 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	39 TON		
0017	2209000000-E	838	ENDWALLS	2 CY		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2		
				EA		
0020	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1		
				EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	180		
				LF		
0022	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	150		
				LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10		
				EA		
0024	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE 350, WEATHERING STEEL)	4		
				EA		
0025	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TYPE III, WEATHERING STEEL)	4		
				EA		
0026	3360000000-E	863	REMOVE EXISTING GUARDRAIL	380		
				LF		
0027	3420000000-E	SP	GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL (WEATHERED STEEL WITH WOOD POSTS)	450		
				LF		
0028	3635000000-E	876	PLAIN RIP RAP, CLASS II	22		
				TON		
0029	3649000000-E	876	PLAIN RIP RAP, CLASS B	39		
				TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	467		
				SY		
0031	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	574		
				SF		
0032	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	154		
				SF		
0033	4425000000-N	1125	WARNING FLAG SETS	4		
				EA		
0034	4445000000-E	1145	BARRICADES (TYPE III)	122		
				LF		
0035	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,200		
				LF		
0036	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	24		
				EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6000000000-E	1605	TEMPORARY SILT FENCE	210 LF		
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	265 TON		
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	165 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	70 LF		
0045	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0046	6029000000-E	SP	SAFETY FENCE	1,235 LF		
0047	6030000000-E	1630	SILT EXCAVATION	380 CY		
0048	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,060 SY		
0049	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	445 SY		
0050	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0051	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0052	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
0053	6087000000-E	1660	MOWING	1.5 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	610800000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0058	611400000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0059	611700000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
0060	801700000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+33.50 -L-)	Lump Sum	L.S.	
0061	802100000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+33.50 -L-)	Lump Sum	L.S.	
0062	808400000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ***** (1, 17+33.50 -L-)	Lump Sum	L.S.	
0063	810554000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	6 LF		
0064	810564000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	32 LF		
0065	811140000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	12 LF		
0066	811500000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0067	811600000-E	SP	CSL TUBES	192 LF		
0068	812100000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+33.50 -L-)	Lump Sum	L.S.	
0069	814700000-E	420	REINFORCED CONCRETE DECK SLAB	5,896 SF		
0070	816100000-E	420	GROOVING BRIDGE FLOORS	6,141 SF		
0071	818200000-E	420	CLASS A CONCRETE (BRIDGE)	110.7 CY		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+33.50 -L-)	Lump Sum	L.S.	
0073	821700000-E	425	REINFORCING STEEL (BRIDGE)	21,792 LB		
0074	823800000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,691 LB		
0075	826500000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	771.33 LF		
0076	836400000-E	450	HP12X53 STEEL PILES	120 LF		
0077	846800000-E	460	ONE BAR METAL RAIL	374.67 LF		
0078	851700000-E	460	1'-**"X ***** CONCRETE PARA- PET (1'-0" X 1'-6")	389.83 LF		
0079	860800000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	280 TON		
0080	862200000-E	876	FILTER FABRIC FOR DRAINAGE	310 SY		
0081	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0082	869200000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0083	899000000-N	SP	CONTRACT TIME	800 DOL		

0924/Jan07/Q55302.03/D416678380000/E83

Total Amount Of Bid For Entire Project :

C201164 (B-3350)
Iredell County

2/16/99

Contract No: C201164
County: Iredell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General