

PROJECT NO.	SHEET NO.	TOTAL NO.
13CR.10591.3, 13CR.20591.2 13CR.305916.2, ETC.	6	8

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	4685000000-E	4686000000-E	4810000000-E
														4" X 90 M THERMO LF	4" X 120 M THERMO LF	4" PAINT LF
13CR.10591.3	McDowell	1	NC 226	US 221 TO NC 226A	1	1.32	22	66	3	1,913		115	352	13,939	13,939	
TOTAL FOR PROJ NO. 13CR.10591.3						1.32		66	3	1,913		115	352	13,939	13,939	
13CR.20591.2	McDowell	2	SR 1221	SR 1214 TO US 70	2	0.51	20	26	1		546	36	112			21,542
		3	SR 1536	SR 1539 TO US 70	2	2.76	18	138	6		2,663	173	450			116,582
		4	SR 1559	SR 1556 TO END OF MAINT	2	0.62	18	31	1		598	39	6			26,188
		5	SR 1560	US 221 TO BEGIN BST	2	3.38	18	169	7		3,262	212	51			142,772
		6	SR 1569	SR 1560 TO US 221	2	0.4	18	20	1		386	25				16,896
		7	SR 1760	SR 1755 TO SR 1747	2	2.69	18	135	5		2,783	181	420			113,626
		8	SR 1168	I-40 TO US 221	2	1.01	18	51	2		968	63	160			42,662
TOTAL FOR PROJ NO. 13CR.20591.2						11.37		570	23		11,206	729	1,199			480,268
13CR.305916.2	McDowell	9	SR 1195	END C&G TO MARION WCL	2	0.87	20	44	2		932	61	9			37,468
TOTAL FOR PROJ NO. 13CR.305916.2						0.87		44	2		932	61	9			37,468
13CR.10611.3	Mitchell	10	NC 197	WEST END OF SR 1312 TO SR 1304	1	2.45	20	123	5	2,959		178	25	25,872	25,872	
		11	NC 197	SR 1350 NORTHWARDLY 0.70 MILES	1	0.7	20	35	1	764		46	5	7,392	7,392	
TOTAL FOR PROJ NO. 13CR.10611.3						3.15		158	6	3,723		224	30	33,264	33,264	
13CR.20611.2	Mitchell	12	SR 1265	SR 1142 TO END MAINT.	2	0.84	18	42	2		811	53	100			35,482
		13	SR 1277	SPRUCE PINE C.L. TO END MAINT.	2	0.21	20	11	0		225	15	40			8,870
		14	SR 1288	SR 1277 TO END MAINT.	2	0.2	17	10	0		182	12	30			8,448
		15	SR 1167	SR 1250 TO SR 1164	2	1.31	18	66	3		1,264	82	13			56,334
		16	SR 1190	NC 226A TO NC 226	2	0.98	18	49	2		946	61	50			41,396
TOTAL FOR PROJ NO. 13CR.20611.2						3.54		178	7		3,428	223	233			150,530
13CR.306124.1	Mitchell	17	US 19 E	END OF 4 LANE TO ECL SPRUCE PINE	1	0.4	28	20	1	610		37	4	4,224	4,224	
TOTAL FOR PROJ NO. 13CR.306124.1						0.4		20	1	610		37	4	4,224	4,224	
GRAND TOTAL						20.65		1,036	41	6,246	15,566	1,389	1,827	51,427	51,427	668,266