

STATE OF NORTH CAROLINA  
 DIVISION OF HIGHWAYS

**SUMMARY OF EARTHWORK**  
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
-L-					
16+00.00 TO 36+70.13	3266		2970		296
-Y-					
10+27.00 TO 13+19.00	6		4756	4750	
-Y1-					
10+29.00 TO 11+47.80	62				62
-Y2A-					
14+77.00 TO 35+74.00	3782		2773		1009
-Y3-					
19+40.00 TO 22+61.83	0		6	6	
-Y4A-					
10+12.00 TO 22+37.28	6906		613		6293
-Y6-					
10+17.12 TO 12+70.01	142		458	316	
<b>PROJECT TOTALS</b>	<b>14164</b>		<b>11576</b>	<b>5072</b>	<b>7660</b>
<b>LOSS DUE TO CLEARING &amp; GRUBBING (PER GEOTECHNICAL)</b>	<b>- 800</b>				<b>- 800</b>
<b>EARTH TO REPLACE BORROW</b>				<b>- 5072</b>	<b>- 5072</b>
<b>GRAND TOTAL</b>	<b>13364</b>			<b>0</b>	<b>1788</b>
<b>SAY</b>	<b>13500</b>				<b>1800</b>

ESTIMATED UNDERCUT EXCAVATION 900 CY  
 ESTIMATED DRAINAGE DITCH EXCAVATION 3360 CY

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, REMOVAL OF EXISTING ASPHALT PAVEMENT, AND SHOULDER BORROW WILL BE PAID FOR AT THE LUMP SUM PRICE FOR "GRADING".