

County : Surry, Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	2,335 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	63.84 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	11,218 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	52,119 SY		
0006	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,545 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	27,515 TON		
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,896 TON		
0009	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	6,433 TON		
0010	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	650 TON		
0011	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,327 TON		
0012	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	173 TON		
0013	2830000000-N	858	ADJUSTMENT OF MANHOLES	26 EA		
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	30 EA		
0015	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	346,162 LF		
0016	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	219,120 LF		
0017	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	160 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	100 LF		
0019	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	266 LF		
0020	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	8 EA		
0021	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	34 EA		
0022	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,200 LF		
0023	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,344 EA		
0024	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0025	6084000000-E	1660	SEEDING & MULCHING	31.67 ACR		
0026	7288000000-E	1715	TRENCHING (PAVED)	75 LF		
0027	7300000000-E	1715	TRENCHING (UNPAVED)	75 LF		
0028	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	750 LF		

0745/Jan13/Q701658.51/D97464200000/E28

Total Amount Of Bid For Entire Project :

C201407  
COUNTIES: SURRY, & YADKIN

2/16/99

Contract No: C201407  
Counties: Surry, & Yadkin

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General