

SUMMARY OF EARTHWORK IN CUBIC YARDS

SURVEY LINE	STATION	STATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT + %	BORROW	WASTE
-L-	32 + 30.83	42 + 95.77	311		13,166	12,855	0
BRIDGE							
SUBTOTAL			311		13,166	12,855	0
BRIDGE							
-L-	44 + 67.91	56 + 72.17	2,256		1,543	0	713
SUBTOTAL			2,256		1,543	0	713
PROJECT SUBTOTALS			2,567		14,709	12,855	713
LOSS DUE TO CLEARING AND GRUBBING			-620			+ 620	
EARTH WASTE TO REPLACE BORROW						-713	-713
PROJECT TOTALS			1,947		14,709	12,762	0
EST. 5% FOR REPLACING TOP SOIL ON BORROW PITS						638	
GRAND TOTAL			1,947			13,400	
SAY			2,000			13,450	

DRAINAGE DITCH EXCAVATION = 21 CY
 UNDERCUT EXCAVATION = 500 CY (CONTINGENCY)

NOTE: APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING". (SEE PROJECT SPECIAL PROVISIONS.)