

TEMPORARY PAVEMENT MARKING SCHEDULE AND QUANTITIES

SYMBOL	DESCRIPTION	PAY ITEM/ QUANTITY BREAKDOWN	TOTAL QUANTITY
PAVEMENT MARKING LINES			
REMOVABLE TAPE (4")			
RA	WHITE EDGELINE	494 ft.	
RI	YELLOW DOUBLE CENTER LINE	494 ft.	
			TOTAL 988 ft.
PAINT (4")			
PA	WHITE EDGELINE	8702 ft.	
PI	YELLOW DOUBLE CENTER LINE	8304 ft.	
			TOTAL 17006 ft.
PAINT (24")			
P4	WHITE STOP BAR	52 ft.	
			TOTAL 52 ft.
PAVEMENT MARKERS			
TEMPORARY RAISED			
MH	YELLOW & YELLOW	58 EA	
			TOTAL 58 EA

	TEMPORARY PAVEMENT MARKING SCHEDULE							
	SCALE: NONE							
	DATE: 4/2004	<table border="1"> <tr> <th colspan="2">REVISIONS</th> </tr> <tr> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> </tr> </table>	REVISIONS					
	REVISIONS							
DWG. BY: KWB DESIGN BY: KWB REVIEWED BY: TRH	CADD FILE							

RECEIVED FROM: FASD/PO BOX 3028 RALEIGH, NC 27622 TEL: 919.788.0224 FAX: 919.788.0232