

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS
 ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200863

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+17.35)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	60	CY	UNDERCUT EXCAVATION
0195000000-E	265	60	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	60	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	10	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0402000000-E	310	72	LF	48" RC PIPE CULVERTS, CLASS III
0708000000-E	310	16	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0995000000-E	340	36	LF	PIPE REMOVAL
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1489000000-E	610	333	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	250	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B
1519000000-E	610	376	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	50	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	45	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	12	EA	RIGHT OF WAY MARKERS
2209000000-E	838	12	CY	ENDWALLS
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29
3030000000-E	862	300	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III

ItemNumber	Sec #	Quantity	Unit	Description
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3628000000-E	876	35	TON	PLAIN RIP RAP, CLASS I
3656000000-E	876	230	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4025000000-E	901	5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
4072000000-E	903	13	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4102000000-N	904	1	EA	SIGN ERECTION, TYPE E
4155000000-N	907	7	EA	DISPOSAL OF SIGN SYSTEM, U- CHANNEL
4412000000-E	SP	554	SF	WORK ZONE SIGNS (STATIONARY)
4412200000-E	SP	124	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4430000000-N	1130	10	EA	DRUMS
4446100000-E	SP	152	LF	BARRICADES (TYPE III)
4685000000-E	1205	1,640	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	1,640	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4900000000-N	1252	21	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	600	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	110	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	50	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	0.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
6029000000-E	SP	250	LF	SAFETY FENCE

ItemNumber	Sec #	Quantity	Unit	Description
6030000000-E	1630	250	CY	SILT EXCAVATION
6036000000-E	1631	900	SY	MATting FOR EROSION CONTROL
6042000000-E	1632	20	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	0.5	ACR	SEEDING & MULCHING
6087000000-E	1660	0.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	0.5	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL