

EARTHWORK SUMMARY

5/10

PROJECT: B-3266		COUNTY: WILKES			DONE BY: RCB		DATE: 9/27/04		CHKD BY: SCL		DATE: 12/8/04		
LOCATION	EXCAVATION (CUBIC METERS)				EMBANKMENT (CUBIC METERS)				BORROW	WASTE (CUBIC METERS)			
	TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUITABLE UNCLASS.	SUITABLE UNCLASS.	TOTAL EMBANKMENT	ROCK EMBANKMENT	EARTH EMBANKMENT		EMBANKMENT PLUS %	ROCK	SUITABLE	UNSUITABLE
<b>(-L-)</b>													
10+40.000 TO 12+18.626 (BR.)	3,591	120			3,471	252	120	102	237			3,354	3,354
END BENT 1						7		7	8	8			
END BENT 2						46		46	53	53			
12+77.000 (BR.) TO 14+46.008	1,311				1,311	853		853	981			330	330
<b>(-DR1-)</b>													
10+05.000 TO 10+36.080	572				572							572	572
<b>(-DR2-)</b>													
10+03.710 TO 10+28.000	148				148							148	148
<b>(-DR3-)</b>													
10+00.000 TO 10+20.950	72				72							72	72
<b>TOTALS</b>	5,694	120			5,574	1,158	120	1,008	1,279	61		4,476	4,476
LOSS DUE TO C & G	-100				-100							-100	-100
SHOULDER BORROW						260		260	299	299			
WASTE IN LIEU OF BORROW										-360		-360	-360
<b>PROJECT TOTALS</b>	5,594	120			5,474	1,418	120	1,268	1,578	0		4,016	4,016
<b>GRAND TOTALS</b>	5,594	120			5,474	1,418	120	1,268	1,578	0		4,016	4,016
<b>SAY</b>	5,600												
DRAINAGE DITCH EXCAVATION = 50 CUBIC METERS													
ESTIMATED UNDERCUT EXCAVATION = 500 CUBIC METERS													