



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201120

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0022000000-M	225	5,600	M3	UNCLASSIFIED EXCAVATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+47.813)
0050000000-M	226	0.4	HA	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-M	226	500	M3	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0080000000-M	SP	1,000	MTN	CLASS IV SUBGRADE STABILIZATION
0134000000-M	240	50	M3	DRAINAGE DITCH EXCAVATION
0195000000-M	265	1,000	M3	SELECT GRANULAR MATERIAL
0196000000-M	270	1,000	M2	FABRIC FOR SOIL STABILIZATION
0318000000-M	300	33	MTN	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0345000000-M	310	10.8	M	600MM SIDE DRAIN PIPE
0366000000-M	310	2.4	M	375MM RC PIPE CULVERTS, CLASS III
0372000000-M	310	19.2	M	450MM RC PIPE CULVERTS, CLASS III
0378000000-M	310	19.2	M	600MM RC PIPE CULVERTS, CLASS III
0384000000-M	310	50.4	M	750MM RC PIPE CULVERTS, CLASS III
0995000000-M	340	49.8	M	PIPE REMOVAL
1121000000-M	520	100	MTN	AGGREGATE BASE COURSE
1220000000-M	545	80	MTN	INCIDENTAL STONE BASE
1489000000-M	610	1,040	MTN	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-M	SP	440	MTN	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-M	620	74	MTN	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-M	654	16	MTN	ASPHALT PLANT MIX PAVEMENT REPAIR
2000000000-N	806	20	EA	RIGHT OF WAY MARKERS

ItemNumber	Sec #	Quantity	Unit	Description
2022000000-M	815	221	M3	SUBDRAIN EXCAVATION
2033000000-M	815	100	M3	SUBDRAIN FINE AGGREGATE
2044000000-M	815	240	M	150MM PERFORATED SUBDRAIN PIPE
2055000000-M	815	24	EA	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	2	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-M	815	4	M	150MM OUTLET PIPE (SUBDRAINS)
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-M	846	15	M	SHOULDER BERM GUTTER
3030000000-M	862	80.01	M	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3559000000-M	866	160	M	** STRAND BARBED WIRE FENCE WITH POSTS (4)
3649000000-M	876	25	MTN	PLAIN RIP RAP, CLASS B
3656000000-M	876	664	M2	FILTER FABRIC FOR DRAINAGE
4412000000-M	SP	8	M2	WORK ZONE SIGNS (STATIONARY)
4412100000-M	SP	9	M2	WORK ZONE SIGNS (PORTABLE)
4412200000-M	SP	6	M2	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	30	EA	DRUMS
4446100000-M	SP	24	M	BARRICADES (TYPE III)
4450000000-N	1150	64	HR	FLAGGER
4810000000-M	1205	3,248	M	PAINT PAVEMENT MARKING LINES (100MM)
6000000000-M	1605	300	M	TEMPORARY SILT FENCE
6006000000-M	1610	70	MTN	STONE FOR EROSION CONTROL, CLASS A

ItemNumber	Sec #	Quantity	Unit	Description
6009000000-M	1610	405	MTN	STONE FOR EROSION CONTROL, CLASS B
6012000000-M	1610	410	MTN	SEDIMENT CONTROL STONE
6015000000-M	1615	1	HA	TEMPORARY MULCHING
6018000000-M	1620	50	KG	SEED FOR TEMPORARY SEEDING
6021000000-M	1620	0.5	MTN	FERTILIZER FOR TEMPORARY SEEDING
6024000000-M	1622	30	M	TEMPORARY SLOPE DRAINS
6027000000-N	1622	3	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-M	SP	230	M	SAFETY FENCE
6030000000-M	1630	1,515	M3	SILT EXCAVATION
6036000000-M	1631	700	M2	MATting FOR EROSION CONTROL
6038000000-M	SP	500	M2	PERMANENT SOIL REINFORCEMENT MAT
6042000000-M	1632	30	M	6.4MM HARDWARE CLOTH
6070000000-N	SP	12	EA	SPECIAL STILLING BASINS
6084000000-M	1660	1	HA	SEEDING & MULCHING
6087000000-M	1660	0.5	HA	MOWING
6090000000-M	1661	25	KG	SEED FOR REPAIR SEEDING
6093000000-M	1661	0.25	MTN	FERTILIZER FOR REPAIR SEEDING
6096000000-M	1662	50	KG	SEED FOR SUPPLEMENTAL SEEDING
6108000000-M	1665	1.75	MTN	FERTILIZER TOPDRESSING
6114000000-N	SP	1	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6123000000-M	1670	0.15	HA	REFORESTATION