

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200671

| ItemNumber | Sec # | Quantity | Unit | Description |
|-------------|-------|----------|------|---|
| 000100000-N | 800 | Lump Sum | | MOBILIZATION |
| 002900000-N | SP | Lump Sum | | REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+07.50) |
| 004300000-N | 226 | Lump Sum | | GRADING |
| 005000000-E | 226 | 1 | ACR | SUPPLEMENTARY CLEARING & GRUB-BING |
| 005700000-E | 226 | 200 | CY | UNDERCUT EXCAVATION |
| 013400000-E | 240 | 30 | CY | DRAINAGE DITCH EXCAVATION |
| 019600000-E | 270 | 100 | SY | FABRIC FOR SOIL STABILIZATION |
| 036600000-E | 310 | 36 | LF | 15" RC PIPE CULVERTS, CLASS III |
| 122000000-E | 545 | 50 | TON | INCIDENTAL STONE BASE |
| 129700000-E | 607 | 125 | SY | MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2") |
| 148900000-E | 610 | X 160 | TON | ASPHALT CONC BASE COURSE, TYPE B25.0B |
| 152500000-E | SP | X 95 | TON | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A |
| 156000000-E | 620 | X 14 | TON | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 |
| 169300000-E | 654 | 55 | TON | ASPHALT PLANT MIX, PAVEMENT REPAIR |
| 200000000-N | 806 | 8 | EA | RIGHT OF WAY MARKERS |
| 228600000-N | 840 | 2 | EA | MASONRY DRAINAGE STRUCTURES |
| 236700000-N | 840 | 2 | EA | FRAME WITH TWO GRATES, STD 840.29 |
| 255600000-E | 846 | 64 | LF | SHOULDER BERM GUTTER |
| 303000000-E | 862 | 600 | LF | STEEL BM GUARDRAIL |
| 315000000-N | 862 | 5 | EA | ADDITIONAL GUARDRAIL POSTS |
| 321500000-N | 862 | 4 | EA | GUARDRAIL ANCHOR UNITS, TYPE III |
| 327000000-N | SP | 4 | EA | GUARDRAIL ANCHOR UNITS, TYPE 350 |
| 364900000-E | 876 | 1 | TON | PLAIN RIP RAP, CLASS B |
| 365600000-E | 876 | 570 | SY | FILTER FABRIC FOR DRAINAGE |

| ItemNumber | Sec # | Quantity | Unit | Description |
|-------------|-------|----------|------|---|
| 441200000-E | SP | 379 | SF | WORK ZONE SIGNS (STATIONARY) |
| 441220000-E | SP | 119 | SF | WORK ZONE SIGNS (BARRICADE MOUNTED) |
| 442500000-N | 1125 | 4 | EA | WARNING FLAG SETS |
| 444610000-E | SP | 86 | LF | BARRICADES (TYPE III) |
| 468500000-E | 1205 | 1,600 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) |
| 468600000-E | 1205 | 1,600 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) |
| 490000000-N | 1252 | 12 | EA | PERMANENT RAISED PAVEMENT MARKERS |
| 600000000-E | 1605 | 485 | LF | TEMPORARY SILT FENCE |
| 606000000-E | 1610 | 150 | TON | STONE FOR EROSION CONTROL, CLASS A |
| 600900000-E | 1610 | 90 | TON | STONE FOR EROSION CONTROL, CLASS B |
| 601200000-E | 1610 | 160 | TON | SEDIMENT CONTROL STONE |
| 601500000-E | 1615 | 1.5 | ACR | TEMPORARY MULCHING |
| 601800000-E | 1620 | 50 | LB | SEED FOR TEMPORARY SEEDING |
| 602100000-E | 1620 | 0.25 | TON | FERTILIZER FOR TEMPORARY SEEDING |
| 602400000-E | 1622 | 50 | LF | TEMPORARY SLOPE DRAINS |
| 602700000-N | 1622 | 2 | EA | INLET PROTECTION AT TEMPORARY SLOPE DRAINS |
| 602900000-E | SP | 200 | LF | SAFETY FENCE |
| 603000000-E | 1630 | 235 | CY | SILT EXCAVATION |
| 603600000-E | 1631 | 590 | SY | MATTING FOR EROSION CONTROL |
| 607000000-N | SP | 6 | EA | SPECIAL STILLING BASINS |
| 608400000-E | 1660 | 1.5 | ACR | SEEDING & MULCHING |
| 608700000-E | 1660 | 1 | ACR | MOWING |
| 609000000-E | 1661 | 50 | LB | SEED FOR REPAIR SEEDING |
| 609300000-E | 1661 | 0.25 | TON | FERTILIZER FOR REPAIR SEEDING |
| 609600000-E | 1662 | 50 | LB | SEED FOR SUPPLEMENTAL SEEDING |
| 610800000-E | 1665 | 1.25 | TON | FERTILIZER TOPDRESSING |

| ItemNumber | Sec # | Quantity | Unit | Description |
|-------------|-------|----------|------|------------------------------|
| 611400000-N | SP | 2 | HR | SPECIALIZED HAND MOWING |
| 611700000-N | 1675 | 8 | EA | RESPONSE FOR EROSION CONTROL |