

PROJECT NO.	SHEET NO.	TOTAL NO.
12CR.10491.2, ETC.	6	7

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1 1/2" TO 4" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA
12CR.10491.2	Iredell	1	US 64	FROM SR 2320 TO DAVIE COUNTY LINE (OMIT 0.45 MILES AT BRIDGE)	1	8.63	VAR 22-44	360	17.26				11,300	565	712	2,230		
<b>TOTAL FOR PROJ NO. 12CR.10491.2</b>						<b>8.63</b>		<b>360</b>	<b>17.26</b>				<b>11,300</b>	<b>565</b>	<b>712</b>	<b>2,230</b>		
12CR.20491.3	Iredell	2	SR 1115	FROM SR 1100 TO DEAD END	2	2.93	20	75				1754	3,196	145	276	285		
		3	SR 2208/2176	FROM SR 2158 TO DEAD END	3	0.70	20	36				419	1,211	60	95	120		
		4	SR 1880	FROM SR 1892 TO SR 1858	3	2.35	20	96					2,564	126	162	252		
		5	SR 1177	FROM SR 1100 TO SR 1238	2	1.25	20	129				748	1,364	65	118	130		
		6	SR 1458	FROM SR 1177 TO SR 1177	2	2.12	20	123				1269	2,313	105	200	205		
		7	SR 3006	FROM SR 1100 TO DEAD END	3	1.36	20	40					1,484	73	94	145		
		8	SR 1186	FROM SR 1128 TO DEAD END	2	0.36	20	69				216	393	20	34	40		
		9	SR 1321/1330	FROM SR 1303 TO END OF MAINTENANCE	2	2.12	20	75				1269	2,313	100	200	230		
<b>TOTAL FOR PROJ NO. 12CR.20491.3</b>						<b>13.60</b>		<b>643</b>	<b>0</b>			<b>5675</b>	<b>14,838</b>	<b>694</b>	<b>1,179</b>	<b>1,407</b>		
12CR.304926.1	Iredell	10	SR 1117	FROM US 21 TO NC 115	3	0.60	VAR 24-38		1.2	14200	540		2,200	110	139	250	21	5
		11	NC 150	FROM MCLLELLAND AVE. (OLD NC 152) TO NC 115	4	0.77	31											
					5	1.29	60						4,200	250	267	400	5	10
<b>TOTAL FOR PROJ NO. 12CR.304926.1</b>						<b>2.66</b>		<b>0</b>	<b>1.2</b>	<b>14200</b>	<b>540</b>	<b>0</b>	<b>6,400</b>	<b>360</b>	<b>406</b>	<b>650</b>	<b>26</b>	<b>15</b>
12CR.304931.2	Iredell	12	US 21	FROM US 64 TO SR 2185	3	0.24	24											
					4	0.70	VAR 30-40											
					6	0.72	VAR 50-60	15		14500	420		3,772	200	239		24	15
<b>TOTAL FOR PROJ NO. 12CR.304931.2</b>						<b>1.66</b>		<b>15</b>	<b>0</b>	<b>14500</b>	<b>420</b>	<b>0</b>	<b>3,772</b>	<b>200</b>	<b>239</b>		<b>24</b>	<b>15</b>
<b>GRAND TOTAL</b>						<b>26.55</b>		<b>1018</b>	<b>18.46</b>	<b>28,700</b>	<b>960</b>	<b>5675</b>	<b>36,310</b>	<b>1,819</b>	<b>2,536</b>	<b>4,287</b>	<b>50</b>	<b>30</b>