

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,018 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	18.46 SMI		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 4")	28,700 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	960 SY		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	5,675 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	36,310 TON		
0008	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	1,819 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,536 TON		
0010	1704000000-E	SP	PATCHING EXISTING PAVEMENT	4,287 TON		
0011	2830000000-N	858	ADJUSTMENT OF MANHOLES	50 EA		
0012	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	30 EA		
0013	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	95,394 LF		
0014	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	103,089 LF		
0015	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	50 LF		
0016	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	598 LF		
0017	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	14 EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	179 EA		
0019	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	501,031 LF		
0020	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,776 EA		
1421/Feb09/Q783535.46/D56517100000/E20			Total Amount Of Bid For Entire Project :			

C201424
COUNTY: IREDELL

2/16/99

Contract No: C201424
County: Iredell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General