8/17/99

PROJECT REFERENCE NO.	SHEET NO.
B-3682 & W-3413	UC-7
DESIGNED BY: VM	
DRAWN BY: VM	
CHECKED BY: GYS	
APPROVED BY: GYS	
REVISED:	
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION	
PROJECT SERVICES UNIT PHONE:(919)250-4128 FAX:(919)250-4119	UTILITY CONSTRUCTION PLANS ONLY

NORTH CAROLINA PROFESSIONAL SEAL 023948 ENGINEER GREG Y. STEVENS 12-16-04

UTILITY CONSTRUCTION

NAD 83

-L-
PI Sta 98+91.32
△ = 25° 21' 25.7" (RT)
D = 6° 45' 00.0"
L = 375.66'
T = 190.96'
R = 848.83'
SE= SEE PLANS

-L-
PI Sta 107+89.82
△ = 56° 48' 37.6" (RT)
D = 6° 30' 00.0"
L = 874.01'
T = 476.71'
R = 881.47'
SE= SEE PLANS

ALL WATER LINES ARE OWNED BY ONSLOW COUNTY PUBLIC UTILITIES

MAKE CONNECTIONS USING NECESSARY FITTINGS

PROP. 1341' - 8" PVC WATER PIPE, SDR 21, 200# WP
PROP. 347' - ¾" PE WATER TUBING, SDR 9, 200# WP
PROP. (12) - ¾" CORPORATION STOP
PROP. (12) - 8" X ¾" TAPPING SADDLE
PROP. (16) - RELOCATE EXIST. WATER METER

ABANDON 8" PVC WATER PIPE

DO NOT DISTURB SEPTIC LINES

SADIE E. MORTON
DB 691 PG 263
MB 26 PG 86,198

DONALD R. CROOM
DB 954 PG 483
MB 26 PG 198

TAMMY CLARK MORTON
DB 2001PG 908

FLOYD R. BUFFINGTON
DB 1505 PG 632
MB 26 PG 198

JONATHAN D. RASMUSSEN
DB 1313 PG 430
MB 32 PG 66

JEFFERY L. LAMBERT
DB 1302 PG 220
MB 33 PG 153

CHARLES E. FRANKLIN
DB 863 PG 273

JAMES V. ROSE
DB 1220 PG 523
DB 1356 PG 681
MB 34 PG 163

SPECIAL CUT DITCH SEE DETAIL A
SPECIAL LATERAL 'V' DITCH SEE DETAIL E
SPECIAL CUT DITCH SEE DETAIL N
CL RIPRAP 17 TONS 38 SY FF
REMOVE
8" PVC-W
8" PVC C900 DR 21
15" RCP
12" GRAVEL
4" CONC
6' WD
2SFD
1SFD
ISBD
CONC PAD
RAILROAD TIES
WOODS
PDE
PDE ROW
TIE FILL SLOPE TO NATURAL GROUND AT EXISTING DITCH

PTSta.100+76.02

PCSta.103+13.11

PCSta.97+00.36

MATCHLINE -L- STA. 96+00.00 SEE SHEET UC-6

MATCHLINE -L- STA. 109+00.00 SEE SHEET UC-8

08-DEC-2004 08:00
R:\Utility Relocation\Proj\B3682 UC\B3682_ut_UC_Rdwg09_UC07.psh
mmoore at DOT12261