

PROJECT NO.	SHEET NO.	TOTAL NO.
5C.092027, ETC.	18	19

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENT. STONE BASE TONS	SHOULDER RECON. SMI	1½" MILLING SY	0" TO 3" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	PG 64-22 PLANT MIX TONS	PG 70-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	5" MONOLITHIC CONCRETE ISLAND SY	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	SEED & MULCHING AC	INDUCTIVE LOOP LF	
5CR.10921.5	Wake	1	NC50	FROM CONSTRUCTION JOINT AT I-540 TO WESTERHAM DR.	1	4.75	23	48	9.5			128			8,574		514		748				6.89		
TOTAL FOR PROJ NO. 5CR.10921.5						4.75		48	9.5			128			8,574		514		748				6.89		
5CR.309208.5	Wake	2	NC50	FROM US70 TO SR2812 TIMBER DR.	2	1.5	28	15	1.5	1,000					2,645		159		165		9	2	2.17	100	
TOTAL FOR PROJ NO. 5CR.309208.5						1.5		15	1.5	1,000		0			2,645		159		165		9	2	2.17	100	
5CR.309203.5	Wake	3	SR3977 CARY PARKWAY	FROM KILDAIRE FARM RD. TO COORSDALE DR.	6	0.8	48					270			2,487		149		118		4	7			
TOTAL FOR PROJ NO. 5CR.309203.5						0.8		0	0	0		270			2,487		149		118		4	7			
5CR.309220.5	Wake	4	SR1829 STRICKLAND RD.	FROM NC50 TO SR1822 LEESVILLE RD.	1	2.77	24	28	5.54			135			4,537		272		305		1		3.99		
		5	SR1012 WESTERN BLVD.	FROM SR3700 GORMAN ST. TO CONSTRUCTION JOINT NEAR MOOREHEAD SCHOOL	7,8	1.66	48	8	5.68				5,022		5,517		547		183	7	1	3	8.30		
		6	SR1005 - SIX FORKS RD.	FROM RAMBLEWOOD TO SR2018 MILLBROOK RD.	5	1.81	45				67,700				6,314		379		55		35	17		1,200	
TOTAL FOR PROJ NO. 5CR.309220.5						6.24		36	11.22	0	67,700	135	5,022		16,368		1,198		543	7	37	20	12.29	1,200	
5CR.20921.5	Wake	7	SR1393 HILLTOP-NEEDMORE RD.	FROM US401 TO SR1301 SUNSET LAKE RD.	1	3.39	20	34	6.78			115			3,796		228		373				4.92		
		8	SR1901 OLD WEAVER RD.	FROM SR1904 - CASH RD. TO DURHAM CO. LINE	12	3.1	20	30	6.2			100			5,145		309		250				4.50		
		9	SR2049 FORESTVILLE RD.	FROM SR2217 OLD MILBURNIE RD. TO SR2215 BUFFALO RD.	3	1.49	24	15	2.98			315	1,480		3,259	64	196		234				2.16		
		10	SR2555 AUBURN-KNIGHTDALE RD.	FROM NEUSE RIVER BRIDGE TO SR2511 GRASSHOPPER RD.	1	1.97	20	20	3.94			115			2,149		129		437				2.86		
		11	SR1141 NEW HILL - OLIVE CHAPEL RD.	FROM US 64 TO SR1011 OLD US1	3	4.24	24	42	8.48			135	4,211		5,545		514		466				6.15		
		12	SR1605 GREEN LEVEL WEST RD.	FROM NC 55 TO SR1600 GREEN LEVEL CHURCH RD.	4	1.99	24	20	3.98	165		135		5,163	3,035		425		200		1	6	2.89		
		13	SR1621 - GREEN HOPE SCHOOL RD.	FROM NC55 TO SR1600 GREEN-LEVEL CHURCH RD.	4	1.89	24	19	3.78			135		3,753	2,614		333		220				2.74		
TOTAL FOR PROJ NO. 5CR.20921.5						18.07		180	36.14	165	0	1,050	5,691	8,916	22,284	3,259	2,002	196	2,180		1	6	26.22		
5C.092027	Wake	14	SR1605 - GREEN LEVEL WEST RD.	FROM NC55 TO SR1600 GREEN LEVEL CHURCH RD.	4	1.99	4						1,200				52								
		15	SR1621 - GREEN HOPE SCHOOL RD.	FROM NC55 TO SR1600 GREEN-LEVEL CHURCH RD.	4	1.89	4						2,454				106								
TOTAL FOR PROJ NO. 5C.092027						3.88		0	0	0	0	0	3,654	0	0	0	158	0	0						
GRAND TOTAL						35.24		279	58.36	1,165	67,700	1,583	14,367	8,916	52,358	3,259	4,180	196	3,754	7	51	35	47.57	1,300	