

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200969

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+47.50)
003600000-E	225	200	CY	UNDERCUT EXCAVATION
004300000-N	226	Lump Sum		GRADING
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
019600000-E	270	200	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	7	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
038400000-E	310	60	LF	30" RC PIPE CULVERTS, CLASS III
148900000-E	610	200	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	370	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	33	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
200000000-N	806	9	EA	RIGHT OF WAY MARKERS
255600000-E	846	170	LF	SHOULDER BERM GUTTER
257000000-N	SP	1	EA	MODIFIED CONCRETE FLUME
303000000-E	862	600	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
364900000-E	876	10	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	170	SY	FILTER FABRIC FOR DRAINAGE
407200000-E	903	45	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
412900000-N	906	3	EA	RELOCATE SIGN, TYPE ***** (E)
415500000-N	907	7	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL

ItemNumber	Sec #	Quantity	Unit	Description
419200000-N	907	3	EA	DISPOSAL OF SUPPORT, U-CHANNEL
441200000-E	SP	485	SF	WORK ZONE SIGNS (STATIONARY)
441220000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	4	EA	WARNING FLAG SETS
444610000-E	SP	72	LF	BARRICADES (TYPE III)
468500000-E	1205	1,600	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
468600000-E	1205	1,600	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
490000000-N	1252	10	EA	PERMANENT RAISED PAVEMENT MARKERS
600000000-E	1605	1,020	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	140	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	65	TON	SEDIMENT CONTROL STONE
601500000-E	1615	1	ACR	TEMPORARY MULCHING
601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
602400000-E	1622	50	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
602900000-E	SP	790	LF	SAFETY FENCE
603000000-E	1630	300	CY	SILT EXCAVATION
603600000-E	1631	995	SY	MATTING FOR EROSION CONTROL
604200000-E	1632	75	LF	1/4" HARDWARE CLOTH
608400000-E	1660	1	ACR	SEEDING & MULCHING
608700000-E	1660	0.5	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING

ItemNumber	Sec #	Quantity	Unit	Description
610800000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
611400000-N	SP	2	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL