

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	9,000 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+13.50)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	240 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	65 SF		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	60 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0015	0345000000-E	310	24" SIDE DRAIN PIPE	44 LF		
0016	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	36 LF		
0017	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	56 LF		
0018	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")	212 LF		

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	52 LF		
0020	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	60 LF		
0021	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	68 LF		
0022	0995000000-E	340	PIPE REMOVAL	526 LF		
0023	1121000000-E	520	AGGREGATE BASE COURSE	335 TON		
0024	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0025	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	410 TON		
0026	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	575 TON		
0027	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	55 TON		
0028	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0029	1869000000-E	710	***** PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (16")	2 SY		
0030	2000000000-N	806	RIGHT OF WAY MARKERS	16 EA		
0031	2022000000-E	815	SUBDRAIN EXCAVATION	410 CY		
0032	2033000000-E	815	SUBDRAIN FINE AGGREGATE	210 CY		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,200 LF		
0034	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	36 EA		
0035	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	3 EA		

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	18 LF		
0037	2209000000-E	838	ENDWALLS	2 CY		
0038	2220000000-E	838	REINFORCED ENDWALLS	10.6 CY		
0039	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0040	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0041	2486000000-E	SP	GENERIC DRAINAGE ITEM TEMPORARY SANDBAG HEADWALL	402.34 SF		
0042	2556000000-E	846	SHOULDER BERM GUTTER	45 LF		
0043	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	200 LF		
0044	3030000000-E	862	STEEL BM GUARDRAIL	87.5 LF		
0045	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0046	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (BIC)	1 EA		
0047	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0048	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0049	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	1 EA		
0050	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	262.5 LF		
0051	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	3 EA		
0052	3628000000-E	876	PLAIN RIP RAP, CLASS I	13 TON		
0053	3649000000-E	876	PLAIN RIP RAP, CLASS B	200 TON		

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	830	SY	
005E	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	160	SF	
005E	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	128	SF	
0057	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	36	SF	
005E	4430000000-N	1130	DRUMS	42	EA	
005E	4435000000-N	1135	CONES	21	EA	
006C	4446100000-E	SP	BARRICADES (TYPE III)	36	LF	
0061	4450000000-N	1150	FLAGGER	1,800	HR	
0062	4460000000-N	1155	WARNING LIGHTS (TYPE B)	4	EA	
006E	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	1	EA	
0064	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	62	EA	
006E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	21,200	LF	
006E	6000000000-E	1605	TEMPORARY SILT FENCE	550	LF	
0067	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	195	TON	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	290	TON	
007C	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0071	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0073	6024000000-E	1622	TEMPORARY SLOPE DRAINS	65 LF		
0074	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0075	6029000000-E	SP	SAFETY FENCE	990 LF		
0076	6030000000-E	1630	SILT EXCAVATION	1,015 CY		
0077	6036000000-E	1631	MATTING FOR EROSION CONTROL	890 SY		
0078	6042000000-E	1632	1/4" HARDWARE CLOTH	610 LF		
0079	6070000000-N	SP	SPECIAL STILLING BASINS	2 EA		
008C	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0081	6087000000-E	1660	MOWING	1 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
008E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
008E	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0087	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
008E	6123000000-E	1670	REFORESTATION	0.7 ACR		

County : Avery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0089	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17 + 13.50 -L-)	Lump Sum	L.S.	
009C	8105500000-E	SP	***.*** DIA DRILLED PIERS IN SOIL (2'-6")	66.5 LF		
0091	8105600000-E	SP	***.*** DIA DRILLED PIERS NOT IN SOIL (2'-6")	34.5 LF		
0092	8111000000-E	SP	PERMANENT STEEL CASING FOR ***.*** DIA DRILLED PIER (2'-6")	60.3 LF		
0093	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0094	8116000000-E	SP	CSL TUBES	464 LF		
009E	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17 + 13.50 -L-)	Lump Sum	L.S.	
009E	8161000000-E	420	GROOVING BRIDGE FLOORS	2,553.1 SF		
0097	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	26.7 CY		
009E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17 + 13.50 -L-)	Lump Sum	L.S.	
0099	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,460 LB		
010C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,496 LB		
0101	8503000000-E	460	CONCRETE BARRIER RAIL	90.29 LF		
0102	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	74 TON		
0103	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	82 SY		
0104	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Avery

---

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0105	8762000000 E	430	3 0 X 1 9 PRESTRESSED CONC CORED SLABS	495 LF		
0106	8892000000 E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	2 847 SF		

---

1500/Mar11/Q64083 53/D423151100000/E106

Total Amount Of Bid For Entire Project :

---

C201456 (B-3808)  
COUNTY: Avery County

2/16/99

Contract No: C201456  
County: Avery

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General