COMPUTED BY: BPS DATE: 05/19/03 CHECKED BY: GSB DATE: 04/27/04 PROJECT NO. SHEET NO. U-3302 3-B

9

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

SUMMARY OF EXISTING ASPHALT PAVEMENT REMOVAL

LINE	Station	Station	LOC LT/RT/CL	SY
-Y1-	16+27	16+86	LT	78
			TOTAL:	78 SY
			SAY:	90 SY

SUMMARY OF EXISTING CONCRETE PAVEMENT REMOVAL

LINE	Station	Station	LOC LT/RT/CL	SY
-LPD-	6+42	11+28	RT	1,027
-LPD-	6+42	7+37	LT	104
-LPD-	9+45	11+39	CL	2,005
RAMP TO WOODFIN ST.				831
			TOTAL:	3,967 SY
			SAY:	3,980 SY

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE LUMP SUM PRICE FOR "GRADING".

Embank. **Borrow** Waste Station Station Excav. -Y1- 21+19.34 -Y1- 16+17.01 40 -LPD- 6+10.05 -LPD- 7+72.65 67 -RPD- 5+92.65 -RPD- 10+66.05 541 184 357 SUBTOTAL: 261 397 WASTE IN LIEU OF BORROW: -3 GRAND TOTALS: 655 261 394 700 CY UNDERCUT EXCAVATION = 500 CY

SUMMARY OF EARTHWORK