COMPUTED BY:	DATE:
CHECKED BY:	DATE:

PROJECT REFERENCE NO.SHEET NO.B-38733-B

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
11+40.00 TO 12+66.89 -L-	47	o	381	334	0
12+66.89 TO 13+01.36 -L-	О	o	288	288	0
13+01.36 TO 14+50.00 -L-	38	o	712	674	0
10+30.00 TO 11+60.00 DRIVEWAY	2	О	314	312	0
SUMMARY TOTAL	87	o	1695	1608	0
EST. 5% FOR REPLACEMENT OF					
TOPSOIL AT BORROW PIT				80	
GRAND TOTAL	87			1688	
SAY	90			1700	

SUMMARY OF PAVEMENT REMOVAL

IN SQUARE YARDS

LINE	STATION TO STATION	LOCATION	ASPHALT REMOVAL
-L-	11+50.00 TO 14+50.00	CENTERLINE	600
		SAY	625