

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200916

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
004300000-N	226	Lump Sum		GRADING
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
031800000-E	300	11	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
037800000-E	310	48	LF	24" RC PIPE CULVERTS, CLASS III
071400000-E	310	20	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
072600000-E	310	28	LF	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK
080700000-E	310	2	EA	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
122000000-E	545	50	TON	INCIDENTAL STONE BASE
148900000-E	610	337	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	149	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	25	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
200000000-N	806	14	EA	RIGHT OF WAY MARKERS
228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES
235500000-N	840	2	EA	FRAME WITH GRATE, STD 840.29
255600000-E	846	65	LF	SHOULDER BERM GUTTER
303000000-E	862	200	LF	STEEL BM GUARDRAIL
304500000-E	862	37.5	LF	STEEL BM GUARDRAIL, SHOP CURVED
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
319500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
327000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
364900000-E	876	2	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	157	SY	FILTER FABRIC FOR DRAINAGE

ItemNumber	Sec #	Quantity	Unit	Description
402500000-E	901	16.07	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
407200000-E	903	27	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
410200000-N	904	2	EA	SIGN ERECTION, TYPE E
415500000-N	907	10	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
441200000-E	SP	181	SF	WORK ZONE SIGNS (STATIONARY)
441220000-E	SP	316	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
444610000-E	SP	264	LF	BARRICADES (TYPE III)
481000000-E	1205	2,480	LF	PAINT PAVEMENT MARKING LINES (4")
600000000-E	1605	415	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	145	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	65	TON	SEDIMENT CONTROL STONE
601500000-E	1615	1.5	ACR	TEMPORARY MULCHING
601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
602400000-E	1622	115	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
602900000-E	SP	200	LF	SAFETY FENCE
603000000-E	1630	275	CY	SILT EXCAVATION
603600000-E	1631	455	SY	MATTING FOR EROSION CONTROL
604200000-E	1632	40	LF	1/4" HARDWARE CLOTH
606900000-E	1638	30	CY	STILLING BASINS
608400000-E	1660	1.5	ACR	SEEDING & MULCHING
608700000-E	1660	1	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING

ItemNumber	Sec #	Quantity	Unit	Description
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	1	TON	FERTILIZER TOPDRESSING
611100000-E	SP	200	LF	IMPERVIOUS DIKE
611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

05-OCT-2004 11:04
M:\p\o\j\337\2510\10299
Mestl - AT - 10/21/2299