

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201168

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (23+60-L1-)
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (32+86-L2-)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0314000000-E	SP	450	TON	SELECT MATERIAL, CLASS ***** (VI)
0314000000-E	SP	590	TON	SELECT MATERIAL, CLASS ***** (VII)
0318000000-E	300	80	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0343000000-E	310	72	LF	15" SIDE DRAIN PIPE
0366000000-E	310	40	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	48	LF	18" RC PIPE CULVERTS, CLASS III
0576000000-E	310	264	LF	*** CS PIPE CULVERTS, ***** THICK (48", 0.019")
0576000000-E	310	200	LF	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")
0582000000-E	310	32	LF	15" CS PIPE CULVERTS, 0.064" THICK
0588000000-E	310	80	LF	18" CS PIPE CULVERTS, 0.064" THICK
0636000000-E	310	3	EA	*** CS PIPE ELBOWS, ***** THICK (48", 0.109")
0636000000-E	310	2	EA	*** CS PIPE ELBOWS, ***** THICK (72", 0.138")
0995000000-E	340	609	LF	PIPE REMOVAL
1121000000-E	520	580	TON	AGGREGATE BASE COURSE
1220000000-E	545	100	TON	INCIDENTAL STONE BASE

ItemNumber	Sec #	Quantity	Unit	Description
1489000000-E	610	200	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1514000000-E	610	630	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5A
1560000000-E	620	50	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	15	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	24	EA	RIGHT OF WAY MARKERS
2264000000-E	840	0.13	CY	PIPE PLUGS
2286000000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29
2500000000-E	842	18	CY	CONCRETE RETAINING WALLS
2556000000-E	846	125	LF	SHOULDER BERM GUTTER
2577000000-E	846	590	LF	CONCRETE EXPRESSWAY GUTTER
3030000000-E	862	250	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3180000000-N	862	3	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (III MOD)
3195000000-N	862	3	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
3215000000-N	862	5	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	5	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3380000000-E	862	137.5	LF	TEMPORARY STEEL BM GUARDRAIL
3389100000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY
3649000000-E	876	13	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	1,380	SY	FILTER FABRIC FOR DRAINAGE
4412000000-E	SP	500	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	50	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)

ItemNumber	Sec #	Quantity	Unit	Description
4425000000-N	1125	12	EA	WARNING FLAG SETS
4430000000-N	1130	60	EA	DRUMS
4435000000-N	1135	41	EA	CONES
4446100000-E	SP	100	LF	BARRICADES (TYPE III)
4455000000-N	1150	80	MD	FLAGGER
4465000000-N	1160	4	EA	TEMPORARY CRASH CUSHIONS
4475000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)
4490000000-E	1170	285	LF	PORTABLE CONCRETE BARRIER (ANCHORED)
4730000000-E	1205	5,810	LF	EPOXY PAVEMENT MARKING LINES (4")
4810000000-E	1205	2,800	LF	PAINT PAVEMENT MARKING LINES (4")
4835000000-E	1205	40	LF	PAINT PAVEMENT MARKING LINES (24")
4850000000-E	1205	1,390	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
5492000000-E	SP	52	LF	3/4" PE WATER TUBING, SDR 9, *****WP (200# WP)
6000000000-E	1605	750	LF	TEMPORARY SILT FENCE
6006000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	245	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	320	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	2	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6029000000-E	SP	640	LF	SAFETY FENCE
6030000000-E	1630	455	CY	SILT EXCAVATION
6036000000-E	1631	1,170	SY	MATTING FOR EROSION CONTROL
6038000000-E	SP	440	SY	PERMANENT SOIL REINFORCEMENT MAT
6042000000-E	1632	580	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	3	EA	SPECIAL STILLING BASINS
6084000000-E	1660	3.1	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.25	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	0.25	ACR	REFORESTATION

5/28/99

I:\CA\04_08\02\28_b-3926_r-dj-sum.dgn