GENERAL NOTES

PAVEMENT MARKINGS AND MARKERS

T) INSTALL PAVEMENT MARKINGS AND MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME MARKING MARKER

1. ALL ROADS EPOXY N/A

U) INSTALL TEMPORARY PAVEMENT MARKINGS AND TEMPORARY PAVEMENT MARKERS ON INTERIM LAYERS OF PAVEMENT AS FOLLOWS:

ROAD NAME MARKING MARKER

1. ALL ROADS PAINT N/A

V) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

W) REPLACE ANY PAVEMENT MARKINGS THAT HAVE BEEN OBLITERATED BY THE END OF EACH DAY'S OPERATION.

X) PLACE AT LEAST TWO APPLICATIONS OF PAINT ON NEW ASPHALT WITH TEMPORARY TRAFFIC PATTERNS WHICH WILL REMAIN IN PLACE OVER THREE (3) MONTHS. PLACE ADDITIONAL APPLICATIONS OF PAINT UPON SUFFICIENT DRYING TIME, AS DETERMINED BY THE ENGINEER.

Y) IN THE EVENT A TIE-IN CANNOT BE MADE IN ONE DAYS TIME, BRING THE TIE-IN AREA TO AN APPROPRIATE ROADWAY ELEVATION, AS DETERMINED BY THE ENGINEER. PLACE BLACK ON ORANGE "LOOSE GRAVEL" SIGNS (W8-7) AND BLACK ON ORANGE "PAVEMENT ENDS" SIGNS (W8-3) 500 FT (150m) AND 1000 FT (300m) RESPECTIVELY IN ADVANCE OF THE UNEVEN AREAS. USE DRUMS TO DELINEATE THE EDGE OF ROADWAY ALONG UNPAVED AREAS.

LOCAL NOTES

TIME RESTRICTIONS


1) DO NOT STOP TRAFFIC FOR MORE THAN 15 MINUTES AS FOLLOWS:

OPERATION

ROAD NAME

A. SHIFTING TRAFFIC AND
ANY OPERATION THAT REQUIRES
TRAFFIC TO BE STOPPED


SR 1340



PLANS PREPARED BY:
RUMMEL KLEPPER & KAHL, LLP
consulting engineers

5800 FARINGDON PLACE SLITE 105
RALEIGH, NORTH CAROLINA 27609-3960

DIVISION OF HIGHWAYS



PROJECT NOTES CONTINUED

DATE: 07 /04

DWG. BY: MAC

DESIGN BY: MAC

EVIEWED BY: BKS



REVISIONS

CADD TCP02A.DGN