PROJ. REFERENCE NO.	SHEET NO.
B-3926	X-0

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
21+50.00	3	1
22+00.00	4	4
22+50.00	3	7
23+00.00	2	25

Station L2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
31+00.00	5	0
31+50.00	21	0
32+00.00	8	38
32+50.00	3	38
33+00.00	27	0
33+50.00	82	0
34+00.00	80	0
34+50.00	33	0

Station L1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
24+00.00	2	13
24+50.00	7	25
25+00.00	5	10
25+50.00	1	6

Station L2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
30+50.00	1	3
31+00.00	4	5
31+50.00	5	7
32+00.00	3	13
32+50.00	38	8

Station L2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
33+50.00	28	2
34+00.00	18	1

Station Drive1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	7	2

Station Drive2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	71	0

Station L1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
22+00.00	2	0
22+50.00	9	0
23+00.00	5	0
23+50.00	27	47
24+00.00	68	47
24+50.00	59	0

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, [illegible] and removal of existing pavement will be paid for at the lump sum price for "Grading".