

DIVISION OF HIGHWAYS  
 STATE OF NORTH CAROLINA

**SUMMARY OF EARTHWORK**  
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
SUMMARY #1					
-L- Sta. 10+08.34 (Beg. Const.) TO 10+39.00 (Beg. Bridge)	0		550	550	
-L- Sta. 11+64.00 (End Bridge) TO 12+11.59 (End Const.)	1		286	285	
SUMMARY NO. 1 SUBTOTAL	1		836	835	
SUMMARY #2					
-DRIVE- Sta. 10+11.21 TO 14+33.18	7		3,518	3,511	
SUMMARY NO. 2 SUBTOTAL	7		3,518	3,511	
DRIVE REMOVAL	3,518				3,518
PROJECT SUBTOTAL	3,526		4,354	4,346	3,518
LOSS DUE TO CLEARING AND GRUBBING	-20			20	
EST. 5% FOR REPLACING TOPSOIL ON BORROW PIT				217	
PROJECT TOTAL	3,506		4,354	4,583	3,518
GRAND TOTAL	3,506			4,583	
SAY	3,550			4,600	

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING"

**PAVEMENT REMOVAL**  
 IN SQUARE YARDS

LINE	LT/RT	STATION TO STATION	SQ. YDS
-Y1-	LT/RT	REMOVE 4' +/- ALONG EXIST. RD.	155.3
-Y1-	LT/RT	REMOVE PAVEMENT @ BEG. EXIST. BRIDGE	87.7
-Y1-	LT/RT	REMOVE PAVEMENT AT END EXIST. BRIDGE	86.3
		PROJECT TOTAL	329.3
		SAY	335 SY

CONTINGENCY UNDERCUT = 200 CY  
 CONTINGENCY SELECT MATERIAL CLASS II OR III = 200 CY  
 CONTINGENCY CLASS IV SUBGRADE STABILIZATION = 250 TONS

**RIGHT OF WAY AREA DATA**

PARCEL NO.	PROPERTY OWNERS NAMES	TOTAL ACREAGE	AREA TAKEN	AREA REMAINING RT.	AREA REMAINING LT.	CONST. EASE.	PERM. DRAIN. EASE.	TEMP. DRAIN. EASE.
1	GEORGE MADISON. ET AL	42.59 (AC)	0.15 (AC)	7.18 (AC)	35.26 (AC)	1.17 (AC)		
2	EUGENE B. WALKER. ET AL		0.15 (AC)			0.14 (AC)		

6/4/99  
 01/17/2005  
 R:\Roadway\Proj\B3922-RDY-SUM.dgn