


Soils encountered within the existing SR 1131 roadway embankment generally consist of 1.0 to 8.0 feet of medium stiff to stiff sandy silty clay (A-6, A-7-6) with plasticity indices of 21 or more and greater than 50 percent passing the number 200 sieve.


Shelby Tube Samples

One undisturbed (Shelby Tube) sample was taken at -L- station 25+00 in the residual clay at a depth of 9.3 to 11.3 feet and submitted for Consolidation testing.

Respectfully submitted,



Gregory H. Lewis, TT-III



Robert R. White, TEGS

GHL:RRW:ts