

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201204

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (23+80.00)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	500	CY	UNDERCUT EXCAVATION
0195000000-E	265	700	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	70	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0343000000-E	310	20	LF	15" SIDE DRAIN PIPE
0344000000-E	310	28	LF	18" SIDE DRAIN PIPE
0366000000-E	310	532	LF	15" RC PIPE CULVERTS, CLASS III
0708000000-E	310	68	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1220000000-E	545	25	TON	INCIDENTAL STONE BASE
1489000000-E	610	460	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	400	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	46	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	30	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	11	EA	RIGHT OF WAY MARKERS
2286000000-N	840	7	EA	MASONRY DRAINAGE STRUCTURES
2308000000-E	840	7	LF	MASONRY DRAINAGE STRUCTURES
2355000000-N	840	7	EA	FRAME WITH GRATE, STD 840.29
2474000000-N	SP	Lump Sum		GENERIC DRAINAGE ITEM HAZARDOUS SPILL BASIN

ItemNumber	Sec #	Quantity	Unit	Description
2474000000-N	SP	Lump Sum		GENERIC DRAINAGE ITEM HAZARDOUS SPILL BASIN W/ LEVEL SPREADER
2556000000-E	846	635	LF	SHOULDER BERM GUTTER
2619000000-E	850	35	SY	4" CONCRETE PAVED DITCH
3030000000-E	862	850	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3628000000-E	876	250	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	74	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	1,037	SY	FILTER FABRIC FOR DRAINAGE
4412000000-E	SP	493	SF	WORK ZONE SIGNS (STATIONARY)
4412200000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4446100000-E	SP	64	LF	BARRICADES (TYPE III)
4810000000-E	1205	10,000	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	17	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	2,075	LF	TEMPORARY SILT FENCE
6006000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	240	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	110	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	3	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	170	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS

ItemNumber	Sec #	Quantity	Unit	Description
6029000000-E	SP	1,000	LF	SAFETY FENCE
6030000000-E	1630	870	CY	SILT EXCAVATION
6036000000-E	1631	1,155	SY	MATTING FOR EROSION CONTROL
6038000000-E	SP	50	SY	PERMANENT SOIL REINFORCEMENT MAT
6042000000-E	1632	140	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	4	ACR	SEEDING & MULCHING
6087000000-E	1660	2	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	2.75	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

24-SEP-2004 11:25
R:\V\66666666\B-4327\rdly_tsh.dgn
JBT Thompson AT B0153407