

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14 + 65.00-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	150 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0008	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	64 LF		
0009	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
0010	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	470 TON		
0012	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	212 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	34 TON		
0014	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0015	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0016	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0017	2556000000-E	846	SHOULDER BERM GUTTER	280 LF		

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	3030000000-E	862	STEEL BM GUARDRAIL	325		LF
001E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
002C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
0021	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		EA
0022	3628000000-E	876	PLAIN RIP RAP, CLASS I	6		TON
002E	3649000000-E	876	PLAIN RIP RAP, CLASS B	119		TON
0024	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	804		SY
002E	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	424		SF
002E	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	144		SF
0027	4446100000-E	SP	BARRICADES (TYPE III)	104		LF
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,640		LF
002E	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (IV)	10		TON
003C	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	10		TON
0031	5444000000-E	1510	6" PVC WATER PIPE, SDR ***** (SDR 21, 200# WP)	93.5		LF
0032	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	200		LB
003E	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	2		EA
0034	5888000000-E	SP	GENERIC UTILITY ITEM 8" HDPE WATER PIPE, SDR 9, 200# WP BY DIRECTIONAL BORE	591		LF

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6000000000-E	1605	TEMPORARY SILT FENCE	550 LF		
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	170 TON		
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	255 TON		
003E	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
004C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0041	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0042	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
0044	6029000000-E	SP	SAFETY FENCE	250 LF		
004E	6030000000-E	1630	SILT EXCAVATION	365 CY		
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	850 SY		
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
004E	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
004E	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
005C	6087000000-E	1660	MOWING	1 ACR		
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
005E	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
0057	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14 + 65.00 -L-)	Lump Sum	L.S.	
005E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 65.00 -L-)	Lump Sum	L.S.	
005E	8105500000-E	SP	***.***" DIA DRILLED PIERS IN SOIL (4'-6")	70.58 LF		
006C	8105600000-E	SP	***.***" DIA DRILLED PIERS NOT IN SOIL (4'-6")	13 LF		
0061	8111000000-E	SP	PERMANENT STEEL CASING FOR ***.***" DIA DRILLED PIER (4'-6")	62.18 LF		
0062	8113000000-N	SP	SID INSPECTION	1 EA		
006E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0064	8116000000-E	SP	CSL TUBES	354.33 LF		
006E	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14 + 65.00 -L-)	Lump Sum	L.S.	
006E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,622 SF		
0067	8161000000-E	420	GROOVING BRIDGE FLOORS	4,848 SF		
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	70.9 CY		

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14 + 65.00 -L-)	Lump Sum	L.S.	
007C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	16,609 LB		
0071	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,904 LB		
0072	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	585.67 LF		
0073	8364000000-E	450	HP12X53 STEEL PILES	400 LF		
0074	8503000000-E	460	CONCRETE BARRIER RAIL	295.83 LF		
007E	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	307 TON		
0076	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	341 SY		
0077	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
007E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0901/Apr08/Q44099.99/D405992900000/E78			Total Amount Of Bid For Entire Project :			

C201223 (B-3828)
COUNTY: Cleveland County

2/16/99

Contract No: C201223
County: Cleveland

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)