



TYPE III & TYPE V UNITS SHOWN.



RAIL POST SPACING FOR SPAN D - STAGE 1 TYPE II UNIT SHOWN.



(102 ASSEMBLIES REQUIRED)

NOTES

THE STRUCTURAL CONCRETE ANCHOR ASSEMBLY SHALL CONSIST OF THE FOLLOWING COMPONENTS:

- A. FERRULES SHALL BE MADE FROM STEEL MEETING THE REQUIREMENTS OF AASHTO M169, GRADE 12L14 AND SHALL HAVE A MINIMUM LENGTH OF THREADS OF 2 $\frac{1}{2}$ FOR 1" FERRULES.
- B. WIRE STRUT SHOWN IN THE CONCRETE ANCHOR ASSEMBLY DETAIL IS THE MINIMUM ALLOWABLE SIZE AND SHALL HAVE A MINIMUM TENSILE STRENGTH OF 100,000 PSI.
- C. THE ANCHOR ASSEMBLIES TO BE HOT DIPPED GALVANIZED TO CONFORM TO REQUIREMENTS OF AASHTO M111.
- D. THE COST OF THE ANCHOR ASSEMBLIES IN PLACE SHALL BE INCLUDED IN THE PRICE BID FOR PRESTRESSED CONCRETE CORED SLABS.
- E. FERRUELS TO BE PLUGGED DURING CASTING OF THE CORED SLAB UNITS AS RECOMMENDED BY THE MANUFACTURER.

THE BARK SIDE OF ALL LUMBER USED ON THE TOP RAIL SHALL BE TURNED UP. THE BARK SIDE SHALL BE TURNED TOWARD WALKWAY FOR ALL SIDE RAILS.

ALL FIELD SAW CUT EDGES FOR LUMBER MEMBERS SHALL BE TREATED WITH A PRESERVATIVE SOLUTION COMPATIBLE WITH THE PRESERVATIVE SOLUTION USED TO PRESSURE TREAT THE LUMBER.

PRE-DRILLING BEFORE INSTALLING SCREWS OR BOLTS WILL BE REQUIRED. LUMBER WITH SPLITS DUE TO SCREWING OR BOLTING WILL HAVE CAUSE FOR REJECTION.

THE CONTRACTOR SHALL DETERMINE THE QUANTITY OF FASTNERS AND VARIOUS LUMBER COMPONENTS OF THE WOODEN RAILING.

FOR TYPE A, B AND C DETAILS, SEE "WOODEN RAIL CONNECTION TYPE - ELEVATION" SHEET 4 OF 4 OF "WOODEN RAIL".

SEE "RAILING SYSTEM" SPECIAL PROVISIONS.


POST SPACING FOR THE TYPE III UNITS ARE FOR THE TEMPORARY GUARDRAIL.

> B-3445 PROJECT NO.____ CURRITUCK 24+18.00 -L-STATION:_

SHEET 2 OF 4

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

RAIL POST SPACING, TYPE OF RAIL CONNECTIONS & DETAILS



M. J. OSTRISHKO DATE: 12-12-01

23-JUN-2004 16:46 W:\squadt\b3445\finalplans\b344501wr.dgn

THE #3 BARS ARE INCEDENTAL AND THEIR COST SHALL BE INCLUDED IN THE PRICE BID FOR THE PRESTRESSED

CONCRETE CORED SLABS.

CHECKED BY : T. G. PAYNE DATE: 4-18-02