

10/26/98

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

PROJECT REFERENCE NO. B-3445	SHEET NO. 3
---------------------------------	----------------

Carter Burgess
Consultants in Planning, Engineering, Architecture,
Construction Management and Related Services
5811 Glenwood Avenue, Suite 300
Raleigh, North Carolina 27612

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
000100000-E	200	Lump Sum		CLEARING & GRUBBING .. ACRE(S)
000800000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
002200000-E	225	500	CY	UNCLASSIFIED EXCAVATION
003600000-E	225	7,100	CY	UNDERCUT EXCAVATION
010600000-E	230	15,600	CY	BORROW EXCAVATION
015600000-E	250	1,100	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT
019500000-E	265	1,500	CY	SELECT GRANULAR MATERIAL
019600000-E	270	1,300	SY	FABRIC FOR SOIL STABILIZATION
020600000-E	SP	2,540	SF	TEMPORARY SHORING - BARRIER SUPPORTED
024100000-E	SP	750	SY	GENERIC GRADING ITEM ROCK PLATING
036600000-E	310	112	LF	15" RC PIPE CULVERTS, CLASS III
054600000-E	310	320	LF	*** CAA PIPE CULVERTS, ***** THICK (36", 0.075")
099500000-E	340	80	LF	PIPE REMOVAL
101100000-N	500	Lump Sum		FINE GRADING
112100000-E	520	260	TON	AGGREGATE BASE COURSE
148900000-E	610	600	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	520	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	60	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
169300000-E	654	30	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
228600000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES
236700000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.29
255600000-E	846	290	LF	SHOULDER BERM GUTTER
303000000-E	862	625	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
364900000-E	876	5	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	160	SY	FILTER FABRIC FOR DRAINAGE
441200000-E	SP	148	SF	WORK ZONE SIGNS (STATIONARY)
441210000-E	SP	365	SF	WORK ZONE SIGNS (PORTABLE)
441220000-E	SP	70	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
442500000-N	1125	4	EA	WARNING FLAG SETS
443000000-N	1130	50	EA	DRUMS
443500000-N	1135	30	EA	CONES
444610000-E	SP	80	LF	BARRICADES (TYPE III)
445500000-N	1150	16	MD	FLAGGER
446500000-N	1160	4	EA	TEMPORARY CRASH CUSHIONS
447000000-N	1160	4	EA	RESET TEMPORARY CRASH CUSHIONS
448000000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)
448500000-E	1170	1,580	LF	PORTABLE CONCRETE BARRIER
450000000-E	1170	1,140	LF	RESET PORTABLE CONCRETE BARRIER
468500000-E	1205	2,896	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
468600000-E	1205	2,896	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
481000000-E	1205	10,850	LF	PAINT PAVEMENT MARKING LINES (4")
483500000-E	1205	37	LF	PAINT PAVEMENT MARKING LINES (24")
485000000-E	1205	400	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
490000000-N	1252	34	EA	PERMANENT RAISED PAVEMENT MARKERS
600000000-E	1605	985	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	155	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	300	TON	SEDIMENT CONTROL STONE
601500000-E	1615	0.5	ACR	TEMPORARY MULCHING
601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
602900000-E	SP	300	LF	SAFETY FENCE
603000000-E	1630	370	CY	SILT EXCAVATION
603600000-E	1631	525	SY	MATTING FOR EROSION CONTROL
604200000-E	1632	835	LF	1/4" HARDWARE CLOTH
608400000-E	1660	0.5	ACR	SEEDING & MULCHING
608700000-E	1660	0.5	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	1	TON	FERTILIZER TOPDRESSING
611400000-N	SP	2	HR	SPECIALIZED HAND MOWING
611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
706000000-E	1705	1,300	LF	SIGNAL CABLE
712000000-E	1705	4	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
725200000-E	1710	70	LF	MESSENGER CABLE (1/4")
726400000-E	1710	1,180	LF	MESSENGER CABLE (3/8")
730000000-E	1715	80	LF	TRENCHING (UNPAVED)
732400000-N	1716	2	EA	JUNCTION BOX (STANDARD SIZE)
736000000-N	1720	8	EA	WOOD POLE
737200000-N	1721	4	EA	GUY ASSEMBLY
740800000-E	1722	1	EA	1" RISER WITH WEATHERHEAD
742000000-E	1722	4	EA	2" RISER WITH WEATHERHEAD
744400000-E	1725	400	LF	INDUCTIVE LOOP SAWCUT
745600000-E	1726	1,320	LF	LEAD-IN CABLE
763600000-N	1745	2	EA	SIGN FOR SIGNALS
776800000-N	1751	1	EA	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)
778000000-N	SP	1	EA	DETECTOR CARD (TYPE 2070L)

09:45:47
I:\090017\001-53445\plan\english\b3445.sum
10 MAY 2002