PROJECT REFERENCE NO.	SHEET NO.
R-2552C	EC-17/CONST.15
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

0 0 10

CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 15

NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE-A AND TEMPORARY ROCK SILT CHECKS TYPE-A AT DRAINAGE OUTLETS.

NOTE: TEMPORARY SILT FENCE SHALL BE INSTALLED A MINIMUM OF 1 METER FROM TOE OF FILL IN WETLAND AREAS

ENVIRONMENTALLY SENSITIVE AREA APPLIES 125 BUFFER ZONES 1 AND 2 SEE PROJECT SPECIAL PROVISIONS

JURISDICTIONAL WETLANDS DO NOT DISTURB

DENOTES PAVEMENT TO BE REMOVED

MATCHLINE -Y4- 25+80

NOTE: IN TEMPORARY IMPACT AREAS, VEGETATION IS TO BE HAND CLEARED AND MACHINERY IS TO WORK ON MATS.

- DENOTES MECHANIZED CLEARING
- DENOTES TEMPORARY FILL IN SURFACE WATER
- DENOTES FILL IN SURFACE WATER
- DENOTES FILL IN WETLAND

NOTE: IN TEMPORARY IMPACT AREAS, VEGETATION IS TO BE HAND CLEARED AND MACHINERY IS TO WORK ON MATS.

- DENOTES MECHANIZED CLEARING
- DENOTES TEMPORARY FILL IN WETLAND
- DENOTES FILL IN WETLAND
- DENOTES TEMPORARY FILL IN SURFACE WATER
- DENOTES FILL IN SURFACE WATER

NOTE: IN TEMPORARY IMPACT AREAS, VEGETATION IS TO BE HAND CLEARED AND MACHINERY IS TO WORK ON MATS.

- DENOTES MECHANIZED CLEARING
- DENOTES TEMPORARY FILL IN WETLAND
- DENOTES FILL IN WETLAND
- DENOTES EXCAVATION IN WETLAND
- DENOTES TEMPORARY FILL IN SURFACE WATER

-L2- GRADE SEE PROFILE SHEETS 37,38
-RAMP A- GRADE SEE PROFILE SHEET 42
-RAMP C- GRADE SEE PROFILE SHEET 47
-RAMP D- GRADE SEE PROFILE SHEET 49

MATCHLINE -Y4- 29+60

MATCHLINE -L2- 154+50

EarthTech
A Tyco International Ltd. Company
701 Corporate Center Drive, Suite 475 Raleigh, NC 27607

15-FEB-2005 16:00
d:\projects\rdp\r2552c_rdy\technical 2nd tr\R2552C_RDY_EC_15.DGN