PROJECT REFERENCE NO.	SHEET NO.
R-2552C	UC-7

METRIC

5 0 10

NORTH CAROLINA PROFESSIONAL SEAL 21805 ENGINEER JOHN M. KAMPRATH

UTILITY CONSTRUCTION

ALL WATER AND SEWER LINES OWNED BY JOHNSTON COUNTY

NAD83

MATCHLINE -Y6- 11+40 SEE SHEET UC-14

MATCHLINE -Y5- 10+90 SEE SHEET UC-14

MATCHLINE -Y9- 11+60 SEE SHEET UC-14

MATCHLINE -Y4- 10+25 SEE SHEET UC-6

MATCHLINE -Y4- 13+95 SEE SHEET UC-8

PROP. 360M OF 400MM DI WATER PIPE, PC 1.72 MPA
1 - 400MM 11 1/4° DI BEND
3 - 400MM 45° DI BENDS
CONNECT USING NECESSARY FITTINGS

SEE PROFILE WL1 SHEETS UC-17 & 18

PROP. 63M OF 400MM DI WATER PIPE, PC 1.72 MPA
3 - 400MM 22 1/2° DI BENDS
CONNECT USING NECESSARY FITTINGS

SEE PROFILE WL4 SHEET UC-20

PROP. 307M - FILL OR REMOVE ABANDONED 400MM PIPE, DI WATER

PROP. 1 - REMOVE EXISTING FIRE HYDRANT

PROP. 38M OF 300MM PVC FORCE MAIN SEWER PIPE, SDR 21, 1.38 MPA WP
4 - 300MM 22 1/2° DI BENDS
CONNECT USING NECESSARY FITTINGS

SEE PROFILE FM3 SHEET UC-18

PROP. 37M - FILL OR REMOVE ABANDONED 300MM PIPE, PVC FORCE MAIN

PROP. 307M - FILL OR REMOVE ABANDONED 400MM PIPE, DI WATER

PROP. 1 - BREAK DOWN, PLUG & FILL ABANDONED UTILITY MANHOLE

SEE SHEET UC-16 FOR BOOSTER STATION SITE PIPING

THEODORE JAMES CIHOS DB 1132 PG 64

CARL G YOUNG DB 1590 PG 733

KAY H RIGSBEE DB 977 PG 104

WORTH POUNDS DB 478 PG 245

Prepared by:
EarthTech
A Tyco International Ltd. Company
701 Corporate Center Drive, Suite 475
Raleigh, NC 27607
(919) 854-6200 – (919) 854-6259(fax)

q:\7987.\r-2552c\proj\uc\r2552cuc7.psh
02/09/2005 04:06:15 PM