

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201182

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	261200000-E	848	200	SY	6" CONCRETE DRIVEWAY					
000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	261900000-E	850	12	SY	4" CONCRETE PAVED DITCH					
001100000-E	200	Lump Sum		CLEARING & GRUBBING . ACRE(S)	303000000-E	862	350	LF	STEEL BM GUARDRAIL	545000000-E	1510	8,235	LF	8" PVC WATER PIPE, SDR ***** (SDR 21, 200# WP)
000800000-E	200	2	ACR	SUPPLEMENTARY CLEARING & GRUBBING	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	548000000-E	1510	1,960	LB	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP
002200000-E	225	20,800	CY	UNCLASSIFIED EXCAVATION	321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	549200000-E	SP	1,720	LF	3/4" PE WATER TUBING, SDR 9, *****WP (200# WP)
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (27+85.00)	327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	551000000-E	1510	39	EA	3/4" CORPORATION STOP
003600000-E	225	8,400	CY	UNDERCUT EXCAVATION	338700000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	554000000-E	1510	3	EA	6" GATE VALVE & VALVE BOX, 200# WP
010600000-E	230	32,201	CY	BORROW EXCAVATION	350300000-E	866	23	LF	WOVEN WIRE FENCE, 47" FABRIC	554600000-E	1510	3	EA	8" GATE VALVE & VALVE BOX, *****WP (200# WP)
013400000-E	240	95	CY	DRAINAGE DITCH EXCAVATION	351500000-E	866	7	EA	5" TIMBER FENCE POSTS, 8'-0" LONG	558200000-E	1510	39	EA	***X*** TAPPING SADDLE (8" X 3/4")
015600000-E	250	1,800	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT	353600000-E	866	36	LF	CHAIN LINK FENCE, 48" FABRIC	564800000-N	1510	45	EA	RELOCATE EXISTING WATER METER
017700000-E	250	228	SY	BREAKING OF EXISTING ASPHALT PAVEMENT	354200000-E	866	3	EA	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	566600000-E	1510	2	EA	FIRE HYDRANT, ***** WP (150 #WP)
019500000-E	265	400	CY	SELECT GRANULAR MATERIAL	354800000-E	866	3	EA	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	600000000-E	1605	1,250	LF	TEMPORARY SILT FENCE
019600000-E	270	400	SY	FABRIC FOR SOIL STABILIZATION	356400000-E	866	1	EA	SINGLE GATES, *** HIGH, ** WIDE, ** OPENING (4' HIGH, 10' WIDE, 10' OPENING)	600600000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
020600000-E	SP	600	SF	TEMPORARY SHORING - BARRIER SUPPORTED	362800000-E	876	36	TON	PLAIN RIP RAP, CLASS I	600900000-E	1610	940	TON	STONE FOR EROSION CONTROL, CLASS B
031800000-E	300	298	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	364900000-E	876	119	TON	PLAIN RIP RAP, CLASS B	601200000-E	1610	355	TON	SEDIMENT CONTROL STONE
034300000-E	310	932	LF	15" SIDE DRAIN PIPE	365600000-E	876	1,083	SY	FILTER FABRIC FOR DRAINAGE	601500000-E	1615	21.5	ACR	TEMPORARY MULCHING
034400000-E	310	36	LF	18" SIDE DRAIN PIPE	365900000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	601800000-E	1620	800	LB	SEED FOR TEMPORARY SEEDING
036600000-E	310	48	LF	15" RC PIPE CULVERTS, CLASS III	441200000-E	SP	78	SF	WORK ZONE SIGNS (STATIONARY)	602100000-E	1620	3.25	TON	FERTILIZER FOR TEMPORARY SEEDING
037200000-E	310	248	LF	18" RC PIPE CULVERTS, CLASS III	441210000-E	SP	328	SF	WORK ZONE SIGNS (PORTABLE)	602400000-E	1622	120	LF	TEMPORARY SLOPE DRAINS
037800000-E	310	572	LF	24" RC PIPE CULVERTS, CLASS III	441220000-E	SP	38	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	602700000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
038400000-E	310	272	LF	30" RC PIPE CULVERTS, CLASS III	442500000-N	1125	3	EA	WARNING FLAG SETS	602900000-E	SP	450	LF	SAFETY FENCE
039000000-E	310	232	LF	36" RC PIPE CULVERTS, CLASS III	443000000-N	1130	100	EA	DRUMS	603000000-E	1630	2,550	CY	SILT EXCAVATION
039600000-E	310	192	LF	42" RC PIPE CULVERTS, CLASS III	443500000-N	1135	50	EA	CONES	603600000-E	1631	5,150	SY	MATting FOR EROSION CONTROL
					444610000-E	SP	96	LF	BARRICADES (TYPE III)	604200000-E	1632	140	LF	1/4" HARDWARE CLOTH
										604500000-E	SP	40	LF	*** TEMPORARY PIPE (18")
040200000-E	310	192	LF	48" RC PIPE CULVERTS, CLASS III	445000000-N	1150	720	HR	FLAGGER	604800000-E	SP	30	SY	FLOATING TURBIDITY CURTAIN
070800000-E	310	72	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	446500000-N	1160	1	EA	TEMPORARY CRASH CUSHIONS	608400000-E	1660	24.5	ACR	SEEDING & MULCHING
071400000-E	310	12	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	447000000-N	1160	1	EA	RESET TEMPORARY CRASH CUSHIONS	608700000-E	1660	13	ACR	MOWING
080600000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	448000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	609000000-E	1661	250	LB	SEED FOR REPAIR SEEDING
080700000-E	310	2	EA	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	448500000-E	1170	230	LF	PORTABLE CONCRETE BARRIER	609300000-E	1661	0.75	TON	FERTILIZER FOR REPAIR SEEDING
099500000-E	340	1,674	LF	PIPE REMOVAL	465000000-N	1251	225	EA	TEMPORARY RAISED PAVEMENT MARKERS	609600000-E	1662	500	LB	SEED FOR SUPPLEMENTAL SEEDING
099600000-N	350	10	EA	PIPE CLEAN-OUT	468500000-E	1205	24,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	609900000-E	1665	18.25	TON	FERTILIZER TOPDRESSING
101100000-N	500	Lump Sum		FINE GRADING	468600000-E	1205	25,915	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
122000000-E	545	1,000	TON	INCIDENTAL STONE BASE	471000000-E	1205	120	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	611700000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL
124500000-E	SP	1	SMI	SHOULDER RECONSTRUCTION	472100000-E	1205	12	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	612300000-E	1670	1	ACR	REFORESTATION
148900000-E	610	6,260	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	472500000-E	1205	10	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)					
149800000-E	610	5,182	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	481000000-E	1205	99,830	LF	PAINT PAVEMENT MARKING LINES (4")					
152500000-E	SP	2,652	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	482000000-E	1205	200	LF	PAINT PAVEMENT MARKING LINES (8")					
156000000-E	620	686	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	483500000-E	1205	240	LF	PAINT PAVEMENT MARKING LINES (24")					
169300000-E	654	244	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	484000000-N	1205	24	EA	PAINT PAVEMENT MARKING CHARACTER					
170400000-E	SP	500	TON	PATCHING EXISTING PAVEMENT	484500000-N	1205	20	EA	PAINT PAVEMENT MARKING SYMBOL					
220900000-E	838	20	CY	ENDWALLS	485000000-E	1205	2,000	LF	REMOVAL OF PAVEMENT MARKING LINES (4")					
228600000-N	840	9	EA	MASONRY DRAINAGE STRUCTURES	490000000-N	1252	225	EA	PERMANENT RAISED PAVEMENT MARKERS					
231900000-N	840	2	EA	FRAME WITH GRATE, DETAIL 840.***** (840.16)	530000000-E	1505	1,015	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)					
233000000-N	840	3	EA	FRAME WITH TWO GRATES, DETAIL 840.***** (840.29)	530600000-E	SP	1,015	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)					
235400000-N	840	2	EA	FRAME WITH GRATE, STD 840.22	544400000-E	1510	78	LF	6" PVC WATER PIPE, SDR ***** (SDR 21, 200# WP)					
236300000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.***** (840.22)										
255600000-E	846	325	LF	SHOULDER BERM GUTTER										

5/14/99

02-FEB-2005 13:36
TDGoins - AT b3682.sum