

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000720000-N	SP	FIELD OFFICE	35 MO		
0003	0001000000-M	200	CLEARING & GRUBBING ... HEC-TARE(S)	Lump Sum	L.S.	
0004	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB-BING	0.4 HA		
0005	0022000000-M	225	UNCLASSIFIED EXCAVATION	29,700 M3		
0006	0036000000-M	225	UNDERCUT EXCAVATION	29,200 M3		
0007	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA-TION	2,500 MTN		
0008	0106000000-M	230	BORROW EXCAVATION	98,000 M3		
0009	0134000000-M	240	DRAINAGE DITCH EXCAVATION	8,020 M3		
0010	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	690 M2		
0011	0163000000-M	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	120 M2		
0012	0177000000-M	250	BREAKING OF EXISTING ASPHALT PAVEMENT	1,060 M2		
0013	0195000000-M	265	SELECT GRANULAR MATERIAL	18,000 M3		
0014	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	20,000 M2		
0015	0199000000-M	SP	TEMPORARY SHORING	850 M2		
0016	0234000000-M	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS III	16,500 M3		
0017	0245000000-M	SP	GENERIC GRADING ITEM CONTAMINATED WATER DISPOSAL	600,000 L		
0018	0255000000-M	SP	GENERIC GRADING ITEM EXCAVATION, HAULING & DISPOSAL OF CONTAMINATED SOIL	10,600 MTN		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0318000000-M	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3,040 MTN		
0020	0342000000-M	310	****MM SIDE DRAIN PIPE (750MM)	64.8 M		
0021	0343000000-M	310	375MM SIDE DRAIN PIPE	220.8 M		
0022	0344000000-M	310	450MM SIDE DRAIN PIPE	66 M		
0023	0345000000-M	310	600MM SIDE DRAIN PIPE	46.8 M		
0024	0360000000-M	310	300MM RC PIPE CULVERTS, CLASS III	253.2 M		
0025	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	1,699.2 M		
0026	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	2,117 M		
0027	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	1,271.4 M		
0028	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	1,167.6 M		
0029	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	642 M		
0030	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	346.8 M		
0031	0402000000-M	310	1200MM RC PIPE CULVERTS, CLASS III	654 M		
0032	0708000000-M	310	400MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	21.6 M		
0033	0986000000-M	SP	GENERIC PIPE ITEM 1200MM DI PIPE, CLASS 50	121.2 M		
0034	0986000000-M	SP	GENERIC PIPE ITEM 300MM DI PIPE, CLASS 50	3.6 M		
0035	0986000000-M	SP	GENERIC PIPE ITEM 400MM DI PIPE, CLASS 50	262.8 M		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	0986000000-M	SP	GENERIC PIPE ITEM 450MM DI PIPE, CLASS 50	52.8 M		
0037	0986000000-M	SP	GENERIC PIPE ITEM 600MM DI PIPE, CLASS 50	338.4 M		
0038	0986000000-M	SP	GENERIC PIPE ITEM 750MM DI PIPE, CLASS 50	66 M		
0039	0986000000-M	SP	GENERIC PIPE ITEM 900MM DI PIPE, CLASS 50	229.2 M		
0040	0995000000-M	340	PIPE REMOVAL	2,898 M		
0041	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0042	1022000000-M	SP	SEALING EXISTING PAVEMENT CRACKS	500 KG		
0043	1121000000-M	520	AGGREGATE BASE COURSE	33,600 MTN		
0044	1220000000-M	545	INCIDENTAL STONE BASE	2,000 MTN		
0045	1297000000-M	607	MILLING ASPHALT PAVEMENT, **MM DEPTH (100MM)	2,040 M2		
0046	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,300 MTN		
0047	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	15,700 MTN		
0048	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	28,800 MTN		
0049	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,400 MTN		
0050	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	34,300 MTN		
0051	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,170 MTN		
0052	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,060 MTN		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	1693000000-M	654	ASPHALT PLANT MIX PAVEMENT REPAIR	1,000 MTN		
0054	2022000000-M	815	SUBDRAIN EXCAVATION	276 M3		
0055	2033000000-M	815	SUBDRAIN FINE AGGREGATE	207 M3		
0056	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	500 M		
0057	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	50 EA		
0058	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0059	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	8 M		
0060	2209000000-M	838	ENDWALLS	60.8 M3		
0061	2253000000-M	840	PIPE COLLARS	5 M3		
0062	2264000000-M	840	PIPE PLUGS	3 M3		
0063	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	377 EA		
0064	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	21 M		
0065	2355000000-N	840	FRAME WITH GRATE, STD 840.29	1 EA		
0066	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.**** (840.16)	121 EA		
0067	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	13 EA		
0068	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	50 EA		
0069	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	94 EA		
0070	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	86 EA		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0072	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	4 EA		
0073	2418000000-M	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	50 M		
0074	2473000000-N	SP	GENERIC DRAINAGE ITEM MASONRY DRAINAGE STRUCTURES (SEALED SYSTEM)	25 EA		
0075	2535000000-M	846	*** X ***MM CONCRETE CURB (200MM X 450MM)	3,450 M		
0076	2549000000-M	846	750MM CONCRETE CURB & GUTTER	8,500 M		
0077	2563000000-M	846	***MM CONCRETE GUTTER (600MM)	50 M		
0078	2570000000-N	SP	MODIFIED CONCRETE FLUME	6 EA		
0079	2577000000-M	846	CONCRETE EXPRESSWAY GUTTER	380 M		
0080	2580000000-M	846	CONCRETE VALLEY GUTTER	25 M		
0081	2591000000-M	848	100MM CONCRETE SIDEWALK	3,700 M2		
0082	2598000000-M	848	CONCRETE WHEELCHAIR RAMPS	270 M2		
0083	2612000000-M	848	150MM CONCRETE DRIVEWAY	1,050 M2		
0084	2619000000-M	850	100MM CONCRETE PAVED DITCH	20 M2		
0085	3030000000-M	862	STEEL BM GUARDRAIL	1,184.91 M		
0086	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0087	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0088	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0089	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	3572000000-M	867	CHAIN LINK FENCE RESET	55 M		
0091	3628000000-M	876	PLAIN RIP RAP, CLASS I	750 MTN		
0092	3649000000-M	876	PLAIN RIP RAP, CLASS B	225 MTN		
0093	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	3,550 M2		
0094	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0095	4082000000-M	903	SUPPORTS, WOOD	683 M		
0096	4096000000-N	904	SIGN ERECTION, TYPE D	18 EA		
0097	4102000000-N	904	SIGN ERECTION, TYPE E	81 EA		
0098	4108000000-N	904	SIGN ERECTION, TYPE F	19 EA		
0099	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	13 EA		
0100	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	11 EA		
0101	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	107 EA		
0102	4412000000-M	SP	WORK ZONE SIGNS (STATIONARY)	110 M2		
0103	4412100000-M	SP	WORK ZONE SIGNS (PORTABLE)	45 M2		
0104	4412200000-M	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	9 M2		
0105	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0106	4420000000-N	1120	CHANGEABLE MESSAGE SIGNS	2 EA		
0107	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0108	4430000000-N	1130	DRUMS	600 EA		
0109	4435000000-N	1135	CONES	100 EA		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	4446100000-M	SP	BARRICADES (TYPE III)	40 M		
0111	4455000000-N	1150	FLAGGER	600 MD		
0112	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	2 EA		
0113	4507000000-M	SP	WATER FILLED BARRIER	920 M		
0114	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	4,069 EA		
0115	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	11,000 M		
0116	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	26,500 M		
0117	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	120 M		
0118	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	380 M		
0119	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	30 EA		
0120	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	259 EA		
0121	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	140,790 M		
0122	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	250 M		
0123	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	850 M		
0124	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	60 EA		
0125	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	534 EA		
0126	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	41,800 M		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	4870000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (600MM)	120 M		
0128	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	12 EA		
0129	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	2,940 EA		
0130	4915000000-M	1264	2.1M U-CHANNEL POSTS	3 EA		
0131	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
0132	5300000000-M	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	2,684 MTN		
0133	5306000000-M	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	2,684 MTN		
0134	5318000000-M	1505	PAVEMENT REPAIR FOR UTILITY WORK	35 MTN		
0135	5360000000-M	1510	150MM DI WATER PIPE, PC 2.41MPA	30 M		
0136	5426000000-M	1510	***MM PVC WATER PIPE, SDR **** (75MM, SDR 21, 1.38MPA)	268 M		
0137	5432000000-M	1510	50MM PVC WATER PIPE, SDR 21, 1.38MPA WP	115 M		
0138	5438000000-M	1510	100MM PVC WATER PIPE, SDR 21, 1.38MPA WP	872 M		
0139	5444000000-M	1510	150MM PVC WATER PIPE, SDR 21, 1.38MPA WP	509 M		
0140	5450000000-M	1510	200MM PVC WATER PIPE, SDR 21, 1.38MPA WP	119 M		
0141	5456000000-M	1510	250MM PVC WATER PIPE, SDR 21, 1.38MPA WP	6,350 M		
0142	5480000000-M	1510	DUCTILE IRON WATER PIPE FITTINGS, 1.72MPA MIN WP	12,074 KG		
0143	5510000000-M	1510	20MM CORPORATION STOP	145 EA		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0144	5516000000-M	1510	25MM CORPORATION STOP	1		EA
0145	5534000000-M	1510	***MM GATE VALVE & VALVE BOX, ****MPA WP (100MM, 1.38MPA)	6		EA
0146	5534000000-M	1510	***MM GATE VALVE & VALVE BOX, ****MPA WP (50MM, 1.38MPA)	11		EA
0147	5534000000-M	1510	***MM GATE VALVE & VALVE BOX, ****MPA WP (75MM, 1.38MPA)	9		EA
0148	5540000000-M	1510	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	17		EA
0149	5546000000-M	1510	200MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA)	5		EA
0150	5552000000-M	1510	250MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA)	12		EA
0151	5576000000-M	1510	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (150MM X 150MM, 1.38MPA)	2		EA
0152	5576000000-M	1510	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (200MM X 150MM, 1.38MPA)	1		EA
0153	5576000000-M	1510	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (200MM X 200MM, 1.38MPA)	3		EA
0154	5582000000-M	1510	*** X ***MM TAPPING SADDLE (100MM X 20MM)	16		EA
0155	5582000000-M	1510	*** X ***MM TAPPING SADDLE (100MM X 25MM)	1		EA
0156	5582000000-M	1510	*** X ***MM TAPPING SADDLE (150MM X 20MM)	2		EA
0157	5582000000-M	1510	*** X ***MM TAPPING SADDLE (200MM X 20MM)	9		EA
0158	5582000000-M	1510	*** X ***MM TAPPING SADDLE (250MM X 20MM)	118		EA

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0159	5648000000-N	1510	RELOCATE EXISTING WATER METER	58 EA		
0160	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	7 EA		
0161	5708000000-M	1520	***MM PVC FORCE MAIN SEWER PIPE, ***** (100MM, SDR 21, 1.38MPA)	406 M		
0162	5708000000-M	1520	***MM PVC FORCE MAIN SEWER PIPE, ***** (150MM, SDR 21, 1.38MPA)	4,401 M		
0163	5708000000-M	1520	***MM PVC FORCE MAIN SEWER PIPE, ***** (200MM,SDR 21, 1.38MPA)	1,654 M		
0164	5708000000-M	1520	***MM PVC FORCE MAIN SEWER PIPE, ***** (300MM, C900, DR 14, 1.38MPA)	20.3 M		
0165	5708000000-M	1520	***MM PVC FORCE MAIN SEWER PIPE, ***** (400MM, C900, DR 14, 1.38MPA)	554 M		
0166	5708000000-M	1520	***MM PVC FORCE MAIN SEWER PIPE, ***** (50MM, SDR 21, 1.38MPA)	537 M		
0167	5708000000-M	1520	***MM PVC FORCE MAIN SEWER PIPE, ***** (75MM, SDR 21, 1.38MPA)	999 M		
0168	5756000000-M	1520	DUCTILE IRON SEWER PIPE FITTINGS, 1.72MPA MIN WP	317 KG		
0169	5882000000-N	SP	GENERIC UTILITY ITEM 150MM LINE STOP & PLUG	1 EA		
0170	5882000000-N	SP	GENERIC UTILITY ITEM 200MM LINE STOP & PLUG	3 EA		
0171	5882000000-N	SP	GENERIC UTILITY ITEM 50MM SEWER AIR RELEASE VALVE AND MANHOLE	13 EA		
0172	5888000000-M	SP	GENERIC UTILITY ITEM 20MM PE WATER TUBING, SDR9, 1.38MPA	2,139 M		
0173	6000000000-M	1605	TEMPORARY SILT FENCE	10,000 M		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0174	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	750 MTN		
0175	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	3,300 MTN		
0176	6012000000-M	1610	SEDIMENT CONTROL STONE	2,400 MTN		
0177	6015000000-M	1615	TEMPORARY MULCHING	31.5 HA		
0178	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	1,400 KG		
0179	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	12 MTN		
0180	6024000000-M	1622	TEMPORARY SLOPE DRAINS	60 M		
0181	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5 EA		
0182	6029000000-M	SP	SAFETY FENCE	3,300 M		
0183	6030000000-M	1630	SILT EXCAVATION	3,500 M3		
0184	6036000000-M	1631	MATTING FOR EROSION CONTROL	18,000 M2		
0185	6042000000-M	1632	6.4MM HARDWARE CLOTH	2,460 M		
0186	6045000000-M	SP	***MM TEMPORARY PIPE (600MM)	120 M		
0187	6069000000-M	1638	STILLING BASINS	260 M3		
0188	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0189	6084000000-M	1660	SEEDING & MULCHING	33 HA		
0190	6087000000-M	1660	MOWING	17.5 HA		
0191	6090000000-M	1661	SEED FOR REPAIR SEEDING	400 KG		
0192	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	1.5 MTN		
0193	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	925 KG		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0194	6108000000-M	1665	FERTILIZER TOPDRESSING	56 MTN		
0195	6109200000-M	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (CENTI-PEDE)	0.2 HA		
0196	6111000000-M	SP	IMPERVIOUS DIKE	90 M		
0197	6114000000-N	SP	SPECIALIZED HAND MOWING	8.5 HR		
0198	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	24 EA		
0199	6123000000-M	1670	REFORESTATION	5 HA		
0200	7060000000-M	1705	SIGNAL CABLE	620 M		
0201	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	24 EA		
0202	7132000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)	2 EA		
0203	7264000000-M	1710	MESSENGER CABLE (9.52MM)	175 M		
0204	7288000000-M	1715	TRENCHING (PAVED)	41 M		
0205	7300000000-M	1715	TRENCHING (UNPAVED)	245 M		
0206	7301000000-M	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, *****MM (** CONDUIT) (50MM, 2)	160 M		
0207	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	12 EA		
0208	7360000000-N	1720	WOOD POLE	4 EA		
0209	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0210	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	1 EA		
0211	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	1 EA		
0212	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	1,100 M		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0213	7456000000-M	1726	LEAD-IN CABLE	845 M		
0214	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	2 EA		
0215	7588000000-N	1741	SIGNAL SUPPORT MAST ARM WITH METAL POLE	6 EA		
0216	7590000000-N	SP	DOUBLE MAST ARM WITH METAL POLE	1 EA		
0217	7613000000-N	SP	SOIL TEST	7 EA		
0218	7614000000-M	SP	DRILLED PIER FOUNDATION (***MM DIA) (1219MM)	35 M		
0219	7631000000-N	1744	MAST ARM WITH METAL POLE DE-SIGN	7 EA		
0220	7636000000-N	1745	SIGN FOR SIGNALS	1 EA		
0221	7688000000-N	SP	CABINET BASE ADAPTER	2 EA		
0222	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0223	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	12 EA		
CULVERT ITEMS						
0224	8126000000-N	414	CULVERT EXCAVATION, STA ***** (196+60.650-L-)	Lump Sum	L.S.	
0225	8126000000-N	414	CULVERT EXCAVATION, STA ***** (199+76.780-L-)	Lump Sum	L.S.	
0226	8126000000-N	414	CULVERT EXCAVATION, STA ***** (206+01.869-L-)	Lump Sum	L.S.	
0227	8133000000-M	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	200 MTN		
0228	8196000000-M	420	CLASS A CONCRETE (CULVERT)	261.6 M3		

County : Pamlico

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0229	8248000000-M	425	EPOXY COATED REINFORCING STEEL (CULVERT)	20,468		KG

1128/Apr14/Q1342628.41/D929309420000/E229

Total Amount Of Bid For Entire Project :

C201457 (R-2539C)
COUNTY: Pamlico County

2/16/99

Contract No: C201457
County: Pamlico

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)